

RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

96 MAY 15 AM 8:18

LIBER NO. 2 PAGE NO. 89
ESTHER LEE
REGISTER OF DEEDS
SAMLAC CO., MICHIGAN

For corners in

<u>Sanilac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>13NR 13E</u>	<u>M-13</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A Milletics, in a field survey on March 19 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2			
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M - 13	GLO Notes	Unrecorded Survey 11-05-91
	Found Post	Act 132 None
	Maple 30" N18E 20 Links	Act 74 None
	Hemlock 16" S12W 28 Links	Old Survey Liber None
	Hemlock 9" S30E 6 Links	
	Hemlock 12" N34W 29 Links	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

APPROVED PEER BOARD MEETING
APRIL 30, 1996

M - 13
SE Cor Section 36 T13N-R13E
Found 1/2" Iron Bar in gravel road bed

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M - 13
1/2" iron bar
S20°W 21.25 feet to a nail in a 18" Maple
S45°W 81.30 feet to a nail in a 24" Apple
Souht 45.20 feet to a nail in a 12" Ash
S10°W 23.10 feet to the face of a lagre 4' Rock

Signed by John A Milletics
Michigan License No. 25859
Professional Surveyor
State of Michigan
Land Surveyor
No. 25859

Date April 10, 1996