

**SURVEY & REMONUMENTATION** LIBER 2 PAGE 110

MAR 21 1997

REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

96 DEC 10 AM 11:56

LIBER NO. 2 PAGE NO. 110  
 ESTHER LEE  
 REGISTER OF DEEDS  
 SANILAC CO. MICHIGAN

For corners **COMMISSION**

SANILAC (County)	Located In:	Corner Code #
1. Public Land Survey	T 13N R 14E	B-13 <b>C-13</b>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, JOHN A MILLETICS, in a field survey on May 25, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
- B - 13 GLO Notes  
 40.00 Set 1/4 Post Hemlock 10 N 57 E 33  
 Hemlock 12 N 50 W 15  
 NO Survey in Old Liber  
 Unrecorded survey Dates Oct, 1982  
 Act 74 None, Act 132 None  
 No Road or Drain Comm Records
  - C - 13 GLO Notes  
 80.00 Set Post Cor Beech 10 N83 1/2 E 12  
 Beech 12 N88 1/2 W 33  
 NO Survey in Old Liber  
 Un recorded survey Dated Oct, 1982  
 Act 74 None, Act 132 None  
 No Road or Drain Comm Records

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- B - 13  
 S 1/4 Cor Section 31 T13N-R14E  
 Found 1/2" Iron Bar set at a proportion between the SE and SW Corners
- C - 13  
 SE Cor Section 31 T13N-R14E  
 Found 1/2 Iron Bar set GLO distance from 1" iron bar to west.

APPROVED PEER BOARD MEETING  
12-02-96 *JM*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |                                             |                                          |
|---------------------------------------------|------------------------------------------|
| B-13                                        | C-13                                     |
| S 1/4 Cor Section 31 T13N-R14E              | SE Cor Section 31 T13N-R14E              |
| 1/2" iron Bar in gravel road bed            | 1/2" Iron Bar in gravel Road Bed         |
| North 33.00 feet to a 1/2" Iron Bar         | N45°E 59.05 to a nail in a Power Pole    |
| N05°W 33.40 to a nail in a Power Pole       | S50°W 65.04 to a nail in a 36" Maple     |
| S70°W 70.40 to a nail in a 10" Ash          | S30°W 85.33 to a nail in a 18" Maple     |
| West 13.53 to a 1/2" Iron Bar N1/4 Cor of 6 | West 27.06 to a 1" Iron Bar NE of Sec. 6 |
| West 2465.13 to SW Cor Section 31           | West 2665.00 to S 1/4 Cor Section 31     |

Signed by *John A. Milletics*  
 Surveyor's Michigan License No. 25859

Date Aug 3, 1996

