

MAY 07 1997 LIBER COMMISSION

2 PAGE 92

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

96 DEC 10 AM 11:55

LIBER NO. 2 PAGE NO. 92 ESTHER LEE REGISTER OF DEEDS SANILAC CO. MICHIGAN

For corners in

Sanilac (County)

Located In:

Corner Code ##

- 1. Public Land Survey T 13N R 14E F-13, G-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

I, John A Milletics, in a field survey on June 1, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- F - 13 GLO NOTES NO Survey in Old Liber
40.00 Set 1/4 Section Post Unrecorded Survey dated 9-91 Total Section Run
Tamarack 7 N59W 7 1/2 Act 74 None, Act 132 None
Tamarack 9 N45E 17 No Road or Drain Comm. Records
G - 13 GLO NOTES NO Survey in Old Liber
80.00 Set Post Corner Unrecorded survey dated 9-91 Total Section Run
Beech 9 N81 1/2 E 26 Act 74 None, Act 132 None
Cedar 7 N29 W 21 No Road or Drain Comm Records

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- F - 13 S 1/4 Corner Section 33 T13N-R14E
Found 1/2" Iron Bar in Gravel Road Bed half way between SE and SW Corners
G - 13 SE Corner Section 33 T13N-R14E
Found 1/2 Iron Bar in Gravel Road Bed

APPROVED PEER BOARD MEETING 12-02-96 JM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F - 13 S 1/4 Corner Section 33 T13N-R14E
1/2" Iron Bar In Gravel Road Bed
S05°E 31.60 to a nail in a bell box post
S05°W 86.87 to a nail in a 36" Maple
N60°W 97.30 to a nail in a Power Pole
West 2649.08 feet to the SW Cor Section 32
West 5.28 to a 1/2" iron Bar N 1/4 Corner Section 4
G - 13 SE Corner Section 33 T13N-R14E
1/2" Iron Bar in Gravel Road Bed
S45°E 49.08 to a nail in a bell pole
N50°E 84.40 to a nail in a power pole
N40°W 67.91 to a nail in a power pole
S45°W 47.06 to a nail in a fence post
West 2649.08 to the S 1/4 Corner Section 32

Signed by [Signature] Date Aug 3, 1996
Surveyor's Michigan License No. 25859

Grid table with columns A-M and rows 2-13 containing numbers 1-36.

