

MAY 07 1997 LIBER

2 PAGE 91 REMONUMENTION

RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE 96 DEC 10 AM 11:55
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 91
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO. MICHIGAN

For corners in Sanilac

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 13N R 14E H-13, I-13
T ___ R ___
T ___ R ___
T ___ R ___
- 2. Property Controlling in Section S ___ T ___ R ___
S ___ T ___ R ___
- 3. Miscellaneous Property in Sec. S ___ T ___ R ___
S ___ T ___ R ___

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, JOHN A MILLETICS, in a field survey on June 1, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- H - 13 GLO NOTES NO Survey in Old Liber
40.00 Set 1/4 Section Post Unrecorded Survey dated 3-94 S 1/2 of Section Run
Elm 9 N58E 7 Act 74 None, Act 132 None
Elm 10 N30W 10 No Road or Drain Comm. Records
- I - 13 GLO NOTES No Survey in Old Liber
80.00 Set Post Corner Unrecorded Survey dated 3-94 S 1/2 of Section Run
Tamarack 10 N72E 43 Act 74 None, Act 132 None
Tamarack 8 N56W 13 No Road or Drain Comm Records

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- H - 13
S 1/4 Cor Section 34 T13N-R14E
Found 1/2" Iron Bar in Gravel Road Bed
half way between SE and SW Section Corners
- I - 13
SE Corner Section 34 T13N-R14E
Found 1/2" Iron Bar

APPROVED PEER BOARD MEETING
12-02-96 JM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H - 13
S 1/4 Corner Section 34 T13N-R14E
1/2" Iron Bar in Gravel Road Bed
S30°E 38.57 to a 1/2" iron Bar
S20°E 51.21 to a nail in a 12" Maple
S20°W 66.25 to a nail in a 10" Apple
East 16.83 to a 1/2" Iron Bar N 1/4 Cor Section 3
West 2653.18 feet to the SW Cor Section 34
- I - 13
SE Cor Section 34 T13N-R14E
1/2" Iron Bar in Gravel Road Bed
N60°E 58.73 to a nail in a power pole
S45°W 47.82 to a Bell Box
East 33.66 to a 1/2" Iron Bar in gravel Road Bed
NE Corner Section 3
West 2653.18 to the S1/4 Section

Signed by John A. Milletics
Surveyor's Michigan License No. 25859

Date Aug 4, 1996

