

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

96 DEC 10 AM 11:55

LIBER NO. 2 PAGE NO. 93
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

Sanilac

(County)

Located In:

Corner Code ##

1. Public Land Survey	T 13N R 14E	J-13, K-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	N
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, JOHN A MILLETICS, in a field survey on June 1, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- J - 13 GLO NOTES
40.00 Set 1/4 Section Post
ELM 18 N58E 47
ELM 7 N67W 18
No Survey in Old Liber
Act 74 None, Act 132 None
No Road or Drain Comm Records
- K - 13 GLO NOTES
80.00 Set Post Corner
Black Ash 20 N34 1/2 E 28
Black Ash 16 N84 1/2 W 34
No Survey in Old Liber
Act 74 None, Act 132 None
No Road or Drain Comm Records



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- J - 13
S 1/4 Cor Section 35 T13N-R14E
Found no evidence of corner in Road Bed
Corner set using Proportion on existing fences

- K - 13
SE Corner Section 35 T13N-R14E
Found 1/2" Iron Bar in Gravel Road Bed

APPROVED PEER BOARD MEETING
12-02-96 97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| J - 13
S 1/4 Corner Section 35 T13N-R14E
1/2" Iron Bar in Gravel Road Bed
S10°E 31.45 to a nail in a Bell Post
N10°E 42.60 to a nail in a 12" Ash
S70°E 60.50 to a stop sign
East 36.63 to a 1/2" Iron Bar S 1/4 Cor Section 2
West 2639.32 feet to the SW Cor Section 35 | K - 13
SE Corner Section 35 T13N-R14E
1/2" Iron Bar in Gravel Road Bed
S05°W 20.10 to a Bell Box
South 38.35 to the East Leg of a Road Sign
N20W 33.55 to a Stop Sign
N50°E 39.90 to the West Leg of a Road Sign
S45°E 62.05 to a stop sign
West 2648.50 to the S 1/4 Corner Section 35 |
|--|---|

Signed by [Signature] Date Aug 4, 1996
Surveyor's Michigan License No. 25859