

MAY 07 1997

LIBER COMMISSION

2 PAGE 33

REMONUMENTATION

RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

96 DEC 10 AM 11:55

LIBER NO. 2 PAGE NO. 33 ESTHER LEE REGISTER OF DEEDS SANILAC CO., MICHIGAN

For corners in

Sanilac (County)

Located In:

Corner Code #

Table with 3 columns: Description (Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec.), T/R/S corner codes, and Corner Code # (J-13, K-13).

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

JOHN A MILLETICS, in a field survey on June 1, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J - 13 GLO NOTES: 40.00 Set 1/4 Section Post ELM 18 N58E 47, ELM 7 N67W 18. No Survey in Old Liber, Act 74 None, Act 132 None, No Road or Drain Comm Records.

K - 13 GLO NOTES: 80.00 Set Post Corner Black Ash 20 N34 1/2 E 28, Black Ash 16 N84 1/2 W 34. No Survey in Old Liber, Act 74 None, Act 132 None, No Road or Drain Comm Records.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J - 13: S 1/4 Cor Section 35 T13N-R14E. Found no evidence of corner in Road Bed. Corner set using Proportion on existing fences.

K - 13: SE Corner Section 35 T13N-R14E. Found 1/2" Iron Bar in Gravel Road Bed.

APPROVED PEER BOARD MEETING

12-02-96 JM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J - 13: S 1/4 Corner Section 35 T13N-R14E. 1/2" Iron Bar in Gravel Road Bed. S10°E 31.45 to a nail in a Bell Post, N10°E 42.60 to a nail in a 12" Ash, S70°E 60.50 to a stop sign, East 36.63 to a 1/2" Iron Bar S 1/4 Cor Section 2, West 2639.32 feet to the SW Cor Section 35. K - 13: SE Corner Section 35 T13N-R14E. 1/2" Iron Bar in Gravel Road Bed. S05°W 20.10 to a Bell Box, South 38.35 to the East Leg of a Road Sign, N20W 33.55 to a Stop Sign, N50°E 39.90 to the West Leg of a Road Sign, S45°E 62.05 to a stop sign, West 2648.50 to the S 1/4 Corner Section 35.

Signed by [Signature] Date Aug 4, 1996 Surveyor's Michigan License No. 25859