

RECEIVED FOR RECORD

98 DEC -1 AM 9:09

LIBER NO. 2 PAGE NO. 263

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MICHELE VAN NORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

Sanilac (County)	Located In:	Corner Code #
1. Public Land Survey	T13N R15E	A-4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A. Milletics, in a field survey on Oct 12, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-4 GLO Notes - Hemlock 16 S29W 54; Beech 15 N52W 37
Old Survey Liber - None
L.C.R.C. - None
Act 132 - None
Unrecorded Surveys Dated 3-31-83 , 4-30-87 , 10-7-97
Road Comm - None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-4 W 1/4 Cor Section 7 T13N-R15E
Found 1" Iron Bar in Gravel Road Bed
Accepted as best evidence
North 2651.80 feet to the NW Corner Section 7
South 2686.68 feet to the SW Corner Section 7



APPROVED PEER BOARD MEETING
NOV 30, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-4
W 1/4 Corner Section 7 T13N-R15E
1" Iron Bar
East 50.50 to a nail in a 10" Ash
N75°E 71.35 to a nail in a Power Pole
S45°W 52.65 to a nail in a Wooden Fence Post
S70°W 44.45 to a nail in a Power Pole
North 2651.80 feet to the NW Corner Section 7
South 2686.68 feet to the SW Corner Section 7

SURVEY &
REMONUMENTATION

JAN 15 1999

SECTION

Signed by John A. Milletics
Surveyor's Michigan License No. 25859

Date Nov 19, 98