

RECEIVED FOR RECORD

98 DEC -1 AM 9:10

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 269

For corners in

Sanilac (County)	Located In:	Corner Code #
1. Public Land Survey	T13N R15E	A-10
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

MICHELE VANNORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A. Milletics, in a field survey on Oct 12, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-10 GLO Notes - D1m 12 N3 1/2W 2.94; Lynn 8 N64W 1.69
Old Survey Liber - None
L.C.R.C. - None
Road Comm. None
Recorded Plat Liber 2 Page 13 Showing Corner
Unrecorded Surveys dated - 10-03-78, 9-09-94
Act 132 - None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-10
W 1/4 Corner Section 30 T13N-R15E
Found 5/8" Iron Bar
Accepted as best evidence
North 2651.60 feet to the NW Corner Section 30
South 2648.22 feet to the SW Corner Section 30

APPROVED PEER BOARD MEETING
NOV 30, 1998

91

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-10
W 1/4 Corner Section 30 T13N-R15E
5/8" Iron Bar
East 33.70 feet to a nail in a Fence Post
East 33.00 feet to a 1/2" Iron Bar
S40°E 56.85 feet to a nail in a Telephone Pole
S45°E 68.30 feet to a nail in a Power Pole
West 2.00 feet to the center of Road
North 2651.60 feet to the NW Corner Section 30
South 2648.22 feet to the SW Corner Section 30

SURVEY &
REMONUMENTATION

JAN 15 1999

SECTION

Signed by John A. Milletics
Surveyor's Michigan License No. 25859

Date Nov 19, 98