

RECEIVED FOR RECORD

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

98 DEC -1 AM 9:10

LIBER NO. 2 PAGE NO. 271

For corners in
Sanilac
(County)

Located In:	Corner Code #
T13NR15E	A-12
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

MICHELE VANNORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

I, John A. Milletics, in a field survey on Oct 12, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- A-12 GLO Notes - Beech 9 S8W 25; Beech 9 N73W 28
- Old Survey Liber - None
- Act 132 - Liber 4 Page 516
- Road Comm - None
- Unrecorded survey dated 6-22-78 (Edmands Eng)
- L.C.R.C. - None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A- 12
- W 1/4 Corner Section 31 T13N-R15E
- Found nail as recorded replaced with 1/2 Iron bar with cap
- Accepted as best evidence
- North 2648.20 feet to the NW Corner Section 31
- South 2632.40 feet to the SW Corner Section 31

APPROVED PEER BOARD MEETING
NOV 30, 1998

gm



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-12
- W 1/4 Corner Section 31 T13N-R15E
- 1/2" Iron Bar with cap
- S70°W 39.18 feet to a nail in a Power Pole
- S30°E 92.65 feet to a nail in a 18" Apple Tree
- S80°E 16.40 feet to the west leg of a Road Sign
- North 2648.20 feet to the NW Corner Section 31
- South 2632.40 feet to the SW Corner Section 31

SURVEY &
REMONUMENTATION

JAN 15 1999

SECTION

Signed by *John A. Milletics*
Surveyor's Michigan License No. 25859

Date Nov 19, 98