

MAY 07 1997

LIBER

2 PAGE 95

RECEIVED FOR RECORD

COMMISSION

REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE 96 DEC 10 AM 11:56 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 95 ESTHER LEE REGISTER OF DEEDS SANILAC CO. MICHIGAN

For corners in

Sanilac (County)

Located In:

Corner Code #

- 1. Public Land Survey T 13N R 15E B-13 - C-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13 containing numbers 1-36.

I, John A Milletics, in a field survey on June 8, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- B - 13 GLO Notes: 40.00 Set 1/4 Section Post Hemlock 9 N72 1/2 E 10 Lynn 9 N72 W 17 1/2
C - 13 GLO Notes: 80.00 Set Post Corner Sugar 30 N46 1/2 E 31 Hemock 30 N59W 31

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- B - 13: S 1/4 Cor. Section 31 T13N-R15E Found 1/2" iron bar in gravel road bed in line with 5/8" iron bar to east
C - 13: Found Monu Box 6.0 feet west of pavement centerline as per State Highway Right of Way Book Page 83



APPROVED PEER BOARD MEETING 12-02-96 JM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B - 13: S 1/4 Corner Section 31 T13N-R15E 1/2" iron bar in gravel Road Bed East 43.70 feet to a 5/1" iron Bar S40°E 69.25 feet to a nail in a Power Pole S10°E 37.54 feet to a nail in a Fence Post S20°E 59.00 feet to a Metal Fence Post West 2538.69 feet to the SW Cor of Section 31
C - 13: SE Cor Section 31 T13N-R15E Monu Box S45°E 81.60 feet to a Gas Post East 6.00 feet to the Centerline of Pavement N45°W 52.50 feet to a nail in a Tele Pole N50°E 105.60 feet to a nail in a Power Pole West 2643.18 feet to the S 1/4 Cor Section 31

igned by [Signature] Date Aug 24, 1996 Surveyor's Michigan License No. 25859