

MAY 17 1997
LIBER
COMMISSION

2 PAGE 37

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

96 DEC 10 AM 11:56

LIBER NO. 2 PAGE NO. 37
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in
Sanilac

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 13N R 15E F-13 - G-13
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, John A Milletics, in a field survey on June 9, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- F - 13 GLO Notes No Old Survey Liber
- 40.00 Set 1/4 Section Post No Act 132, No Act 74
- Beech 12 N87E 23 No Road Comm or Drain Comm Notes
- Beech 20 N25W 44 Section Breck Down on unrecorded survey dated 4-28-94
- G - 13 GLO Notes No Old Survey Liber
- 80.00 Set Post Corner No Act 132 - No Act 74
- Hemlock 14 N89E 33 No Road Comm or Drain Comm Notes
- Hemlock 11 N73W 24 1/2 Section Breck down on unrecorded survey dated 4-28-96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- F - 13 S 1/4 Corner Section 33 T13N-R15E
- Found 1/2" iron bar in gravel road bed set on line between SE and SW Cor at 1/2 distance
- G - 13
- SE Corner Section 33 T13N-R15E
- Found 3/4" Pipe in gravel Road Bed 14.52 feet west of 1/2" Iron Bar GLO offset

| | A | B | C | D | E | F | G | H | I | J | K | L |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |



APPROVED PEER BOARD MEETING
12-02-96 *JM*

C. Description of monuments for corner and accessories established to perpetuate locating the position of the corner:

- F - 13 S 1/4 Corner Section 33 T13N-R15E
- 1/2" iron bar 6 feet north of gravel centerline
- East 24.40 feet to a 1/2" Iron Bar
- S20°E 72.30 feet to a nail in a Fence Post
- S30°E 43.09 feet to a nail in a Fence Post
- West 2641.40 feet to the SW Corner Section 33
- East 2641.40 feet to the SE Corner Section 33
- G - 13 SE Corner Section 33 T13N-R15E
- 3/4" iron pipe in gravel Road Bed
- East 14.52 feet to a 1/2" Iron Bar
- N45°W 46.70 feet to a nail in a Tele Pole
- S45°W 36.80 feet to a nail in a Fence Post
- S45°E 80.90 feet to a nail in a Power Pole
- N45°E 44.40 feet to a metal cable post

Signed by John A. Milletics

Date Aug 25, 1996

Surveyor's Michigan License No. 25859