

MAY 07 1997

REMONUMENTION

RECEIVED FOR RECORD

96 DEC 10 AM 11:56

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 100
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

Sanilac Located In: Corner Code #
(County)

- 1. Public Land Survey T13N R 15E L-13 - M-13
T R
T R
T R
- 2. Property Controlling in Section S T R
S T R
- 3. Miscellaneous Property in Sec. S T R
S T R

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
- 5. Private Claims

I, John A Milletics, in a field survey on June 22, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- L-13 GLO Notes
40.00 Set 1/4 Section Post
Hemlock 16 N78E 9
Hemlock 10 N32 1/2 W 21
No Old Survey Liber
No Act 74, Act 132 Liber 2 Page 594
Numerous unrecorded surveys of Liber 2 Page 594
- M-13 GLO Notes
Hemlock 22 S33W 20, Hemlock 18 N55 1/2 E 23
Beech 12 N32E 38, Beech 14 N57W 55 1/2
Beech 11 S14E 31, Hemlock 22 S33W 20
No Old Survey Liber
No Act 74, Act 132 Liber 2 Page 594
Numerous unrecorded surveys of Liber 2 Page 594

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-13
S 1/4 Corner Section 36 T13N-R15E
Found 1/2 Iron Bar in Gravel Road Bed
- M-13
SE Corner Section 36 T13N-R15E
Found 1" Iron Bar in Gravel Road Bed

APPROVED PEER BOARD MEETING
12-02-96 JM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-13 S 1/4 Corner Section 36 T13N-R15E
1/2" Iron Bar in Gravel Road Bed
North 79.55 feet to a nail in a 36" Twin Ash
N45°W 36.80 feet to the East End of a 12" CMP
N65°W 63.50 feet to the West End of a 12" CMP
South 82.25 feet to a nail in a Power Pole
- M-13 SE Corner Section 36 T13N-R15E
1" Iron Bar in gravel Road Bed
N30°W 71.60 feet to a nail in a Power Pole
N30°E 72.10 feet to a nail in a Power Pole
N45°E 44.40 feet to a nail in a Fence Post
S30°E 34.25 feet to a Stop Sign

Signed by John A Milletics
Surveyor's Michigan License No. 25859

Date Sept 28, 1996

