

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

98 DEC -1 AM 9:08

LIBER NO. 2 PAGE NO. 231

For corners in

Sanilac

(County)

Located in:

Corner Code #

- 1. Public Land Survey T13N R16E A-9
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

MICHELE VANNORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, John A. Milletics, in a field survey on Oct 27, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- A-9 GLO Notes - Pine 36 S4W 24; Beech 12 N22W 5 1/2
- Old Survey Liber - Survey dated 1886 by F.F. Rogers
- L.C.R.C. - None
- Act 132 - Liber 4 Page 115 - Liber 2, Page 485
- Road Comm - None

SURVEY & REMONUMENTATION

JAN 15 1999

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A - 9
- SW Corner Section 19 T13N-R16E
- Found 5/8" Iron Bar in Gravel Road Bed
- North 2642.46 feet to the W 1/4 Corner Section 19
- South 2651.11 feet to the W 1/4 Corner Section 30
- Accepted as best evidence

APPROVED PEER BOARD MEETING
NOV 30, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A - 9
- SW Corner Section 19 T13N-R16E
- 5/8" Iron Bar in gravel road Bed
- North 2642.46 feet to the W 1/4 Corner Section 19
- South 2651.11 feet to the W 1/4 Corner Section 30
- N45°E 67.15 feet to a nail in a Power Pole
- N45°W 47.20 feet to a nail in a Anchor Pole
- S25°W 66.30 feet to the NE Corner of a Church
- S25°E 58.70 feet to a nail in a Anchor Pole



Signed by John A. Milletics
Surveyor's Michigan License No. 25859

Date Nov 20, 1998