

RECEIVED FOR RECORD

98 DEC -1 AM 9:08

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 232

MICHELE VANNORMAN  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

For corners in

Sanilac (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>13N</u> R <u>16E</u>	<u>A-10</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John A. Milletics, in a field survey on Oct 27, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														
2	6			5			4			3			2	1
3														
4	7			8			9			10			11	12
5														
6	18			17			16			15			14	13
7														
8	19			20			21			22			23	24
9														
10	30			29			28			27			26	25
11														
12	31			32			33			34			35	36
13														

A. Description of original monument and accessories and/or subsequent restoration:

- 10 GLO Notes - Cedar 5 S47 1/2W 18; Cedar 10 N39W 3
- Old Survey Liber - None
- L.C.R.C. - None
- Act 132 - Liber 2, Page 485
- Road Comm - None

SURVEY & REMONUMENTATION

JAN 15 1999

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A - 10
- W 1/4 Corner Section 30 T13N-R16E
- Found 5/8" Iron Bar in gravel road bed
- North 2651.11 feet to the NW Corner Section 30
- South 2636.22 feet to the SW Corner Section 30
- Accepted as best evidence

SECTION

APPROVED PEER BOARD MEETING  
NOV 30, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A - 10
- W 1/4 Corner Section 30 T13N-R16E
- 5/8" Iron bar in gravel road bed
- North 2651.11 feet to the NW Corner Section 30
- South 2636.22 feet to the SW Corner Section 30
- West 31.20 feet to a nail in a wooden fence post
- East 6.00 feet to the centerline of a gravel road
- S85°W 27.60 feet to a nail in a 24" Maple Tree
- S35°W 59.00 feet to a nail in a 30" Maple Tree



Signed by John A. Milletics  
Surveyor's Michigan License No. 25859

Date Nov 20, 1998