

ENCLOSURE

MAY 07 1997 LIBER

2 PAGE 101

REMONUMENTION

RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

96 DEC 10 AM 11:56

LIBER NO. 2 PAGE NO. 101
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO. MICHIGAN

For corners in

Sanilac (County)	Located In:	Corner Code #
1. Public Land Survey	T 13N R 16E	B-13 C-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

John A. Milletics, in a field survey on June 29, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-13 GLO Notes
 40.00 Set 1/4 Section Post No old Survey Liber
 Birch 16 N54W 32 No Act 132 showing corner No Act 74
 Cedar 20 N72E 16 Information taken form I.E. Choep records

C-13 GLO Notes
 80.00 Set Post Corner No Old Survey Liber
 Sugar 14 N45E 32 No Act 132, No Act 74
 Beech 11 N72 1/2 W 38 Collins Eng. Records

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-13
 S 1/4 Corner Section 31 T13N-R16E
 Found 1/2" Iron Bar in Gravel Road Bed
 Set by I.E.C. on Sectional Breckdown

C-13
 SE Corner Section 31 T13N-R16E
 Found 5/8" Iron Bar in Gravel Road Bed

APPROVED PEER BOARD MEETING
12-02-96 JM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13 S 1/4 Corner Section 31 T13N-R16E	C-13 SE Corner Section 31 T13N-R16E
1/2" Iron Bar in gravel Road Bed	5/8" Iron Bar in gravel Road Bed
N20°W 32.40 to a nail in a 12" Maple	East 73.00 to a 1/2" Iron Bar
N20°E 31.80 to a nail in a 18" Apple	N50°E 66.90 to a nail in a Power Pole
S45°W 47.85 to a nail in a Fence Post	S45°E 43.65 to a nail in a Power Pole
West 2646.68 to SW Cor of Section	S50°W 70.10 to a nail in a 36" Ash
East 2652.94 to SE Cor of Section	West 2652.94 to the S 1/4 Cor
	East 2653.88 to the S 1/4 Cor

Signed by _____
Surveyor's Michigan License No. 25859

Date Nov 15, 1996

