

MAY 07 1997 LIBER

2 PAGE 102

REMONUMENTATION

RECEIVED FOR RECORD

96 DEC 10 AM 11:56

LIBER NO. 2 PAGE NO. 102  
ESTHER LEE  
REGISTER OF DEEDS  
SANILAC CO. MICHIGAN

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Sanilac (County)	Located in:	Corner Code #
1. Public Land Survey	T 13N R 16E	D-13 E-13
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____	Recorded Plat _____	
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, John A Milletics, in a field survey on June 29, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-13 GLO Notes	No Old Survey Liber
40.00 Set 1/4 Section Post	No Act 74, No Act 132
Beech 12 N27W 20 1/2	Unrecorded Collins Survey and I. E. Chope Survey
Beech 6 N31E 10	

E-13 GLO Notes	No Old Survey Liber
80.00 Set Post Corner	No Act 74, No Act 132
Hemlock 9 N81E 17	I. E. Chope unrecorded Survey
Beech 11 N59W 27	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13 S 1/4 Corner Section 32 T13N-R16E  
Found 1/2" Iron Bar in Gravel Road Bed  
at equal distance between SE and SW Cor of Section

E-13 SE Cor Section 32 T13N-R16E  
Found 1" Bar in gravel Road Bed

APPROVED PEER BOARD MEETING

12-02-96 JM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13 S 1/4 Corner Section 32 T13N-R16E	E-13 SE Corner Section 32 T13N-R16E
1/2" iron bar in gravel Road Bed	1" Iron Bar in gravel Road Bed
West 7.10 feet to a 1" Iron Bar	West 34.20 to a 1" Iron bar
S15°E 73.95 to the NW Corner of a House	N50°W 61.75 to a nail in a Power Pole
S05°W 43.30 to a nail in a 10" Pine	S50°W 78.90 to a Bell Box
N70°W 82.95 to a nail in a 36" Maple	N70°W 40.60 to the East Leg of a Road Sign
West 2653.88 to the SW Cor	West 2653.88 to the S 1/4 Cor
East 2653.88 to the SE Cor	East 2654.94 to the S 1/4 Cor

Signed by [Signature]  
Surveyor's Michigan License No. 25859

Date Nov 15, 1996

