

LIBER
MAY 07 1997

REMONUMENTION

RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE 96 DEC 10 AM 11:56
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION

LIBER NO. 2 PAGE NO. 103
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO. MICHIGAN

Sanilac (County)	Located In:	Corner Code #
1. Public Land Survey	T13N R16E	F-13 G-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A Milletics, in a field survey on June 29, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2			1
3												
4	7		8		9		10		11			12
5												
6	10		17		16		15		14			13
7												
8	19		20		21		22		23			24
9												
10	30		29		28		27		26			25
11												
12	31		32		33		34		35			36
13												

- A. Description of original monument and accessories and/or subsequent restoration:
- F-13 GLO Notes
40.00 Set 1/4 Section Post
Beech 13 N38W 26
Beech 13 N53 1/2 E 27 1/2
Old Survey Liber Dated June 1890 by Jeff W. Galbraith
No Act 74, No Act 132
Unrecorded Surveys by I.E. Chope and Collins Eng.
 - G-13 GLO Notes
80.00 Set Post Corner
Hemlock 20 N52 1/2 W 26
Hemlock 20 N55E 32
Old Survey Liber Dated June 1890 by Jeff W. Galbraith
NO Act 74, No Act 132
Unrecorded Surveys I.E. Chope and Collins Eng.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- F-13
S 1/4 Corner Section 33 T13N-R16E
Found 1/2" Iron Bar in gravel Road Bed
- G-13
SE Corner Section 33 T13N-R16E
Found 2" Square Bar

APPROVED PEER BOARD MEETING
12-02-96 JM

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- F-13 S 1/4 Corner Section 33 T13N-R16E
1/2" Iron Bar in gravel Road Bed
West 35.05 to a 1/2" Iron Bar
S60°W 46.50 to a nail in a Tele Pole
S30°W 34.85 to a nail in a 10" Ash
West 2654.94 to the SW Corner of Section
East 2654.94 to the SE Corner of Section
 - G-13 SE Corner Section 33 T13N-R16E
2" Iron Bar in Gravel Road Bed
West 35.63 to a 1/2" Iron Bar
S05°W 11.00 to a nail in a 10" Maple
N05°W 18.00 to a nail in a 12" Ash
North 33.00 to a 1/2" Iron Bar
N05°E 34.20 to a Bell Box
N50°E 41.70 to a nail in a 18" Ash
West 2654.94 to the S 1/4 Cor

Signed by _____
Surveyor's Michigan License No. 25859

Date Nov 15, 1996

