

LIBER MAY 07 1997

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

96 DEC 10 AM 11:56

LIBER NO. 2 PAGE NO. 103  
ESTHER LEE  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

For corners in COMMISSION

Sanilac (County)	Located in:	Corner Code #
1. Public Land Survey	T13N R16E	F-13 G-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____	Recorded Plat _____	
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John A. Milletics, in a field survey on June 29, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- F-13 GLO Notes: 40.00 Set 1/4 Section Post Beech 13 N38W 26 Beech 13 N53 1/2 E 27 1/2
  - G-13 GLO Notes: 80.00 Set Post Corner Hemlock 20 N52 1/2 W 26 Hemlock 20 N55E 32
- Old Survey Liber Dated June 1890 by Jeff W. Galbraith  
No Act 74, No Act 132  
Unrecorded Surveys by I.E. Chope and Collins Eng.
- Old Survey Liber Dated June 1890 by Jeff W. Galbraith  
NO Act 74, No Act 132  
Unrecorded Surveys I.E. Chope and Collins Eng.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13  
S 1/4 Corner Section 33 T13N-R16E  
Found 1/2" Iron Bar in gravel Road Bed

G-13  
SE Corner Section 33 T13N-R16E  
Found 2" Square Bar

APPROVED PEER BOARD MEETING  
12-02-96 JM

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- F-13 S 1/4 Corner Section 33 T13N-R16E: 1/2" Iron Bar in gravel Road Bed West 35.05 to a 1/2" Iron Bar S60°W 46.50 to a nail in a Tele Pole S30°W 34.85 to a nail in a 10" Ash West 2654.94 to the SW Corner of Section East 2654.94 to the SE Corner of Section
  - G-13 SE Corner Section 33 T13N-R16E: 2" Iron Bar in Gravel Road Bed West 35.63 to a 1/2" Iron Bar S05°W 11.00 to a nail in a 10" Maple N05°W 18.00 to a nail in a 12" Ash North 33.00 to a 1/2" Iron Bar N05°E 34.20 to a Bell Box N50°E 41.70 to a nail in a 18" Ash West 2654.94 to the S 1/4 Cor

Signed by [Signature]  
Surveyor's Michigan License No. 25859

Date Nov 15, 1996

