

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 272

For corners in

Sanilac (County)	Located In:	Corner Code #
1. Public Land Survey	T14N R12E	A-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

MICHELE VAN NORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A. Milletics, in a field survey on Oct 20, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.


	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			2
3													
4	7			8			9			10			11
5													
6	18			17			16			15			14
7													
8	19			20			21			22			23
9													
10	30			29			28			27			26
11													
12	31			32			33			34			35
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-13 GLO Notes - Hemlock 12 S59W 11; Beech 10 S79E 20
Old Survey Liber - Survey by F.F. Rogers
Old Survey Liber - Survey by Galbraith
L.C.R.C - Tuscola Co. Records
Act 132 - None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A - 13
Found Concrete Monument with 2" Brass Cap
Accepted as best evidence
East 2135.03 feet to the S 1/4 Corner Section 31



APPROVED PEER BOARD MEETING
NOV 30, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13
Concrete Monument with 2" Brass Cap
N35°E 62.80 to a nail in the SE Face of a Pole
S42°E 37.09 to a nail in a Telephone Pole
S64°W 61.80 to a nail in a Power Pole
N20°W 138.21 to a nail in a Power Pole
East 2135.03 feet to the S 1/4 Corner Section 31

SURVEY &
REMONUMENTATION

JAN 15 1999

SECTION

Signed by John A. Milletics
Surveyor's Michigan License No. 25859

Date Nov 20, 1998