

Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

95 JUL 10 AM 9: 27

LIBER NO. 2 PAGE NO. 55
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in
Sanilac
(County)

Located In: Corner Code #

- 1. Public Land Survey T 14N R 12E C - 13
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John A Milletics, in a field survey on May 5, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C - 13
GLO Notes Set Post at 80 chains Beech 22 N67°E 40 - Hemloch 14 N61°W 29
Act 74 Form None
Act 132 Form None
Road Comm None
Drain Comm None
State Highway Right of Way Book Page 11

Approved Peer Group Meeting May 25, 1995

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C - 13
SE Cor Section 31 T14N-R12E
Found P.K. Nail

SURVEY &
REMONUMENTATION

JUL 31 1995

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C - 13
SE Cor Section 31 T14N-R12E
Monu Box
West 67.93 to a Iron Pipe (NW Cor Section 5 T13N-R12E
N80°W 40.60 to a nail in a 48" Cottonwood
N85°W 21.90 to the south leg of a Road sign
S45°W 55.60 to a nail in a 48" Cottonwood
S45°E 59.60 to a nail in a Fence Post



Signed by John A. Milletics Date May 22, 1995

Surveyor's Michigan License No. 25859