

RECEIVED FOR RECORD

98 DEC -1 AM 9:10

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 274

For corners in

<u>Sanilac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T14N R12E	D-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

MICHELE VAN NORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A. Milletics, in a field survey on Nov 1, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.


	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 13 GLO Notes - Beech 11 N74W 19; Beech 8 N66E 36
- Old Survey Liber - None
- L.C.R.C. - None
- Act 132 - Liber 4, Page 354 (Stewart G Case)
- Road Comm - None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D - 13
S 1/4 Corner Section 32 T14N-R12E
Found T-Bar in Gravel Road Bed-Raised with 1/2" Iron Bar with cap
Accepted as best evidence



APPROVED PEER BOARD MEETING
NOV 30, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D - 13
S 1/4 Corner Section 32 T14N-R12E
1/2" Iron Bar with cap
West 2681.14 feet to the SW Corner Section 32
East 2637.60 feet to the SE Corner Section 32
N65°E 61.80 feet to a nail in a 12" Ash
N50°W 45.05 feet to a nail in a 8" Ash
N70°W 62.65 feet to a nail in a 15" Ash
S70°W 73.65 feet to a nail in a Wooden Fence Post

SURVEY &
REMONUMENTATION

JAN 15 1999

SECTION

Signed by [Signature]
Surveyor's Michigan License No. 25859

Date Nov 20, 1998