

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

98 DEC -1 AM 9:10

LIBER NO. 2 PAGE NO. 279

MICHELE VANNORMAN  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

For corners in

Sanilac  
(County)

Located In:

Corner Code #

1. Public Land Survey

T14N R12E I-13

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. , Recorded Plat

5. Private Claims

I, John A. Milletics, in a field survey on Nov 1, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-13 GLO Notes - Beech 10 N55E 38; Beech 16 N68W 9  
Old Survey Liber - None  
Act 132 - Liber 3 , Page 685  
L.C.R.C. - None  
Road Comm - None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I - 13  
SE Corner Section 34 T14N-R12E  
Found 1/2 " Iron Bar in gravel road bed  
West 2653.58 feet to the S 1/4 Corner Section 34  
East 2660.70 feet to the S 1/4 Corner Section 35  
Accepted as best evidence

APPROVED PEER BOARD MEETING  
NOV 30, 1998



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I - 13  
SE Corner Section 34 T14N-R12E  
1/2" iron Bar with Cap  
West 2653.58 feet to the S 1/4 Corner Section 34  
East 2660.70 feet to the S 1/4 Corner Section 35  
N35°E 73.60 feet to a nail in a Power Pole  
N10°W 38.40 feet to a Stop Sign  
South 17.00 feet to the East Leg of a Road Sign  
N40°E 65.00 feet to a Bell Box

SURVEY &  
REMONUMENTATION

JAN 15 1999

SECTION

Signed by [Signature]  
Surveyor's Michigan License No. 25859

Date Nov 20, 1998