

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 283

MICHELE VANNORMAN  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

For corners in

Sanilac (County)	Located In:	Corner Code #
1. Public Land Survey	T14N R12E	M-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John A. Millettics, in a field survey on Nov 1, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
M-13 GLO Notes - Birch 10 N70 1/2E 14; Maple 8 West 5 1/2  
Old Survey Liber - None  
L.C.R.C. - None  
Act 132 - Liber 2, Page 246 (CASE)  
Road Comm - None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
M - 13  
SE Corner Section 36 T14N-R12E  
Found 5/8" Iron Bar raised with 1/2" Iron Bar  
West 2621.60 feet to the S 1/4 Corner Section 36  
as recorded in Liber 2, Page 246

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M - 13  
SE Corner Section 36 T14N-R12E  
1/2" Iron Bar with cap  
South 32.70 feet to a nail in a Wooden Fence Post  
S05°E 48.40 feet to a nail in a 12" Poplar  
S40°W 38.75 feet to a nail in a Wooden Fence Post  
S65°W 53.50 feet to a nail in a Wooden Fence Post  
West 2621.60 feet to the S 1/4 Corner Section 36



APPROVED PEER BOARD MEETING  
NOV 30, 1998

SURVEY &  
REMONUMENTATION

JAN 15 1999

SECTION

Signed by [Signature]  
Surveyor's Michigan License No. 25859

Date Nov 20, 1998