

RECEIVED FOR RECORD

98 DEC -1 AM 9:09

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 250

For corners in

Sanilac (County)	Located In:	Corner Code #
1. Public Land Survey	T14N R15E	F-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

MICHELE VANNORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A. Millettics, in a field survey on Oct 19, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 13 GLO Notes - Pine 22 N25E 10; W. Ash 7 N82 1/2W 24
- Old Survey Liber - None
- Road Comm - None
- L.C.R.C. - None
- Act 132 - None

SURVEY & REMONUMENTATION

JAN 15 1999

SECTION



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- F - 13
- S 1/4 Corner Section 33 T14N-R15E
- Set 1/2" Iron Bar with cap a equal distance from SE Corner and SW Corner of Section in Line.
- East 2657.94 feet to the SE Corner Section 33
- West 2657.94 feet to the SW Corner Section 33

APPROVED PEER BOARD MEETING
NOV 30, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-13
- S 1/4 Corner Section 33 T14N-R15E
- 1/2" Iron bar with cap
- East 2657.94 feet to the SE Corner Section 33
- West 2657.94 feet to the SW Corner Section 33
- N70°W 112.70 feet to a Bell Box
- N60°W 44.20 feet to the North end of a CMP
- S60°W 45.30 feet to the South end of a CMP
- S70°E 63.70 feet to a nail in a large tree stump
- South 3.00 feet to the centerline of gravel road

Signed by John A. Millettics
Surveyor's Michigan License No. 25859

Date Nov 21, 98