

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

1091814
 LIBER 9267 PAGE 975
 12/27/1999 01:15:00 P.M.
 MACOMB COUNTY, MI
 CARMELLA SABAUGH, REG/DEEDS

For corners in

MACOMB
 (County)

IRA TOWNSHIP
 Located In: Corner Code #

1. Public Land Survey	T <u>3</u> N <u>R</u> 15 E	<u>A-3</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

SURVEY &
 RE-MONUMENTATION

MAR 17 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, ROBERT H. BIRKETT, in a field survey on JULY 10, 1999 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 A-3 IRA 1817, W. PRESTON, GLO. SET WOOD POST.

- (a) 1977, H. KOBBS # 14097, 1" AXLE SHAFT IN MONUMENT BOX, SURVEY, L. 2882, P. 473 M.C.R.
- (b) 1977, H. KOBBS # 14097, 1" AXLE SHAFT IN MONUMENT BOX, L.C.R.C., L. 2882, P. 290 M.C.R.
- (c) 1986, H. AVEY # 15396, 1" AXLE SHAFT IN MONUMENT BOX, L.C.R.C., L. 4353, P. 426 M.C.R.
- (d) 1993, S. DUNN # 28408, FOUND 1" AXLE IN MONUMENT BOX, L.C.R.C., L. 8166, P. 1 M.C.R.
- (e) 1992, R. SMITH # 16052, 1" AXLE SHAFT IN MONUMENT BOX, SURVEY, L. 13, P. 236, S.C.C.R.
- (f) 1994, D. LITTLE # 31596, FOUND DISK IN MONUMENT BOX, SURVEY, L. 15, P. 33, S.C.C.R.
- (g) 1987, M. ROSSOW # 24615, FOUND MONUMENT BOX, SURVEY, L. 10, P. 29, S.C.C.R.
- (h) 1997, R. SMITH # 16052, FOUND 1/2" IRON IN MONUMENT BOX, RECORDED PLAT "NORTH RIDGE SUB.", L.124, P.31-42, M.C.R.
- (i) 1998, J. FENN #23505, REMON DISK IN MON. BOX, RECORDED PLAT "ANDREWS BY THE BAY" L. 130, P. 19-24, M.C.R.
- (j) 1996, R. SMITH #16052, REMON DISK IN MON. BOX, RECORDED PLAT "HARBOR CREEK SUB. No. 1" L. 117, P. 34-37, M.C.R.
- (k) 1996, R. SMITH #16052, REMON DISK IN MON. BOX, RECORDED PLAT "HARBOR CREEK SUB. No. 2" L. 131, P. 37-44, M.C.R.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 A-3 IRA FOUND REMON. CORNER #28408 IN MONUMENT BOX CENTER COUNTY LINE (ASPHALT) .6' DEEP.
 CORNER COMMON TO M-3, CHESTERFIELD TOWNSHIP, T. 3 N., R. 14 E.

N.W. - (a, b, d, i, j 37.62') S.E. CORNER CONCRETE HEADWALL
 S.W. - (a, b, d, i, j 37.34') N.E. CORNER CONCRETE HEADWALL
 RECOVERED CORNER AGREES WITH MEASUREMENTS TO FOUND IRONS IN "NORTH RIDGE SUB", ANDREWS BY THE BAY AND "HARBOR CREEK SUBDIVISION No. 1".

FIELD MEASUREMENTS

A-3 TO A-2
 GLO (1817) - 40 CHAINS (2640')
 M. ROSSOW (1986) - 2691.34'
 R. SMITH (1992) - 2691.34'
 RE-MONUMENTATION (1999) - 2691.62'


A-3 TO A-4
 GLO (1817) - 40 CHAINS (2640')
 R. SMITH (1996) - 2665.33'
 J. FENN (1998) - 2665.34'
 RE-MONUMENTATION (1999) - 2635.56'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 A-3 IRA ACCEPT EXISTING MARKED "MACOMB COUNTY MONUMENT, MI ACT 345, #28408, M-13"
IN EXISTING MONUMENT BOX

- AZ. 25° 34.36' - SET NAIL WITH TAG REMON. IN SOUTHWEST FACE UTILITY POLE.
- AZ. 145° 69.89' - FOUND P.K. WITH TAG # 39096 IN SOUTHWEST FACE UTILITY POLE.
- AZ. 230° 66.57' - SET REMON TAG OVER FOUND (FOUR) CUT CONCRETE NAILS IN SOUTH FACE GUY POLE.
- AZ. 245° 37.30' - NORTHEAST CORNER CONCRETE HEADWALL (DAMAGED).
- AZ. 290° 37.64' - SOUTHEAST CORNER CONCRETE HEADWALL.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Robert H. Birkett Date 23 November 1999
 Surveyor's Michigan License No. 41094



BY THE MACOMB COUNTY SURVEY FEES
 AS THE OFFICIAL CORNER UNDER MICHIGAN
 PUBLIC ACT 345 OF 1990 AT A MEETING HELD
 10/31/99
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

940