



ST. CLAIR COUNTY, MICHIGAN OFFICIAL GOVERNMENT CORNER

MAR 1 5 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

CLERK REGISTER ST. CLAIR COUNT RECEIVED FOR RECORD

	CHINA TOWNSHIP	ner Code #			DEC	2 2) 101	20	_
1. Public Land Survey	T 4N R 16E	J-1	ŧ	IBER_		AGE		IME_	8
in Section	S T R S T R S T R S T R	Re	egister (of Deed	Stam	p & Fi	unn le Nui	mber	
4. Lot No, R	ecorded Plat								
5. Private Claims			A В С	DΕ	F G	Н	l J	К	L
	M_, in a field survey onAUGUST	. 3 (-6-	_5 	_4-	-3-			 - -
19_99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in				8 	9 	—10— 	<u> </u>		12-
conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior,				[17	-16	—15—	- 14		 3-
Bureau of Land Management	or by a decree of a Court of Law and	/or that the 8	—19 —	20	21	-22-	23		24-
•	nes 3, 4 and 5 above were in conforr rd of Land Surveyors or by a Decree o	nance with	30-	29	28		26		25 25
	hed, monumented, re-monumented,	. '' -	—31 —	-32-	33	-34 	35		36-

NOTE: Not more than 1 CORNER, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- J-13, ST. CLAIR TOWNSHIP, 1817, W. PRESTON SURVEY OF GLO (SET A "POST" FOR CORNER)

- 1971, J. LANSKY SURVEY LCRC L.1, P.62 (FOUND A 1/2" IRON ROD & WITNESSED)

 1982, J. LANSKY SURVEY L.8, P.300 (DOES NOT ID CORNER BUT REFERS TO LCRC L.1, P.62)

 1976, J. LANSKY SURVEY L.4, P.86 (ID'S CORNER AS: "IRON ROD" & REFERS TO LCRC L.1, P.62)

 1977, J. LANSKY SURVEY L.5, P.399 (DOES NOT ID CORNER BUT REFERS TO LCRC L.1, P.62)
- (D) ST. CLAIR COUNTY ROAD COMMISSION PLANS & WITNESSES) (E)
- 1990, G. JAMES UNRECORDED SURVEY (ID'S IRON BAR WITH CAP #19835 & REFERS TO LCRC L.1, P.62 & APPLIES WITNESSES)
- 1996, M. ROSSOW UNRECORDED SURVEY (NO ID OF CORNER BUT REFERS TO LCRC L.1, P.62) 1962 OLD COUNTY SURVEYORS RECORD (DOES NOT IDENTIFY FOUND CORNER BUT APPLIES WITNESSES TO A POINT)
- SEE BACK OF SHEET
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A 1/2" IRON ROD WITH RLS LD. CAP #19835 FROM DATA IN PART "A" ABOVE: NORTH 15.0' TO SOUTH EDGE OF 24' PAVEMENT OF FRED W. MOORE HIGHWAY (A)(F)(J)(U)(K) WEST 23.0' TO EAST EDGE OF 10' GRAVEL DRIVE (A) EAST 5' TO WEST EDGE OF 10' GRAVEL DRIVE (A) SOUTH WEST 122.70' TO NORTH EAST CORNER OF HOUSE (#3981) (A)(E)(F)(H)(J)(U)(K) 65.95' SOUTH TO SPIKE IN FENCE POST (F)(J)(U)(K)

THIS CORNER-COMMON TO J-13, ST. CLAIR TOWNSHIP, T.5N., R.16E.

PA 343-1990 PEER COMMITTEE AT 0750 12-15-99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: SET A 2" DIAMETER ALUMINUM CAP WITH MAGNET ATTACHED & INSCRIBED "ST. CLAIR COUNTY OFFICIAL CORNER" ON THE ½" ROD WITH I.D. #19835, WITH THE FOLLOWING WITNESSES: NORTH EAST 124.07" TO COUNTY TAG IN SOUTH LEG OF BILLBOARD OF MICHIG NORTH WEST 117.3 TO COUNTY TAG IN POWER POLE WEST SOUTH WEST 182.16' TO COUNTY TAG IN POWER POLE SOUTH EAST 178.72' TO COUNTY TAG IN POWER POLE SOUTH WEST 122.7' TO NORTH EAST CORNER OF HOUSE NO. 3981 MICHAELJ. **ROSSOW**

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL

LAND SURVEYOR SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER. NO. 24615 LAND 12-17-99 Signed by Date

24615 Surveyor's Michigan License No



ST. CLAIR COUNTY, MICHIGAN OFFICIAL GOVERNMENT CORNER

SURVEY & REMONUNENTATION

MAR 1 5 2000

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

	CHINA TOWNSHIP	Corner Code #	
1. Public Land Survey	T 4N R 16E T R	J-1	
2. Property Controlling S S	_ T R _ T R		
3. Miscellaneous S S	T R T R		Register of Deeds Stamp & File Number

J-1 CHINA TOWNSHIP, IN 1817, W. PRESTON OF GLO SURVEY (SET A "POST" FOR THIS CORNER)

(I) 1994, J. LANSKY SURVEY L.9, P.92 (REFERS TO "IRON ROD" & LCRC L.1, P.62)

(J) 1990, G. JAMES SURVEY L.12, P.97 ("FOUND IRON BAR" WITNESSES & REFERS TO LCRC L.1, P.62)

(K) 1982, R. KREGER SURVEY L.8, P.359 ("FOUND ½" IRON" WITNESSES & REFERS TO LCRC L.1, P.62)

(L) 1978, J. LANSKY SURVEY L.6, P.190 (NO REFERENCE TO CORNER BUT REFERS TO LCRC L.1, P.62)

(M) 1994, J. LANSKY SURVEY L.14, P.485 (FINDS IRON ROD & REFERS TO LCRC L.1, P.62)

(N) 1973, J. LANSKY SURVEY L.2, P.567 (FINDS IRON ROD & REFERS TO LCRC L.1, P.62)

(O) 1987, J. LANSKY SURVEY L.9, P.478 (NO REFERENCE TO CORNER BUT REFERS TO LCRC L.1, P.62)

(O) 1998, J. LANSKY SURVEY L.6, P.302 (NO REFERENCE TO CORNER BUT REFERS TO LCRC L.1, P.62)

(Q) 1979, J. LANSKY SURVEY L.6, P.306 (NO REFERENCE TO CORNER BUT REFERS TO LCRC L.1, P.62)

(R) 1988, J. LANSKY SURVEY L.10, P.109 (FINDS IRON ROD & REFERS TO LCRC L.1, P.62)

(S) 1988, J. LANSKY SURVEY L.10, P.110 (FINDS IRON ROD & REFERS TO LCRC L.1, P.62)

(T) 1990, UNRECORDED SURVEY BY G. JAMES 9REFERS TO "FOUND IRON BAR" WITNESSES & REFERS TO LCRC L.1, P.62)