

ST. CLAIR COUNTY, MICHIGAN  
OFFICIAL GOVERNMENT CORNER

DEC 02 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970



REGISTERED  
ST. CLAIR COUNTY

AUG 21 AM 7:25

RECORDED  
JUN 1

	Located In:	Corner Code #
	ST. CLAIR TWP.	
1. Public Land Survey	T <u>5N</u> R <u>16E</u>	<u>G-1</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Michael J. Rossow, in a field survey on March 31, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 1 CORNER, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

4" CHERRY TREE MARKED AS ORIGINAL CORNER (1817). OLD ST. CLAIR COUNTY SURVEYOR'S RECORD IDENTIFIES NO CORNER.  
ACT 74 CERTIFICATE FILED IN L.2,P.206 IDENTIFIES A 1/2" IRON IN 1974.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" REROD PER ACT 74 CERTIFICATION FILED IN L.2,P.206 RECORDED WITNESSES:

ROAD FENCE N. 25.5'; VERIFIED  
REF. MONUMENT W.N.W. 39.26'; VERIFIED  
VERIFIED CORNER FROM ACT 132 SURVEYS L.6,P.124 (DUNN); L.4,P.80 (COLLINS); L.1,P.371 (COLLINS); L.5,P.392 ALL 3 WITNESSES VERIFIED. L.3,P.227 (DUNN)

PA 345-1990

PEER COMMITT

APPROVED 7-11-9

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET A 2" DIA. ALUMINUM CAP WITH MAGNET ATTACHED & INSCRIBED "ST. CLAIR COUNTY OFFICIAL CORNER" ON THE EXISTING 1/2" REROD AT THE CLOSING CORNER WHICH LIES 1.55' SOUTH OF AND NORMAL TO A LINE BETWEEN THE S.W. CORNER SEC. 32 & THE S. 1/4 CORNER OF SEC. 32, T.6N.,R.16E.

N.N.W. 90.12' PK AND COUNTY TAG IN 10" TWIN ELM  
W.N.W. 159.34' PK AND COUNTY TAG IN 30" MAPLE  
E.S.E. 161.93' PK AND COUNTY TAG IN 48" PINE  
S.W. 78.87' PK AND COUNTY TAG IN 12" CRIMSON MAPLE  
92.98' EAST OF S.W. CORNER SEC. 32, T.6N.,R.16E.

Signed by \_\_\_\_\_ Michael J. Rossow Date August 1, 1997

Surveyor's Michigan License No. 24615

