

ST. CLAIR COUNTY, MICHIGAN
OFFICIAL GOVERNMENT CORNER



DEC 0 2 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

REGISTERED
MAY 21 AM 7:25
REGISTERED DEEDS
ST. CLAIR COUNTY

	Located In:	Corner Code #
	ST. CLAIR TWP.	
1. Public Land Survey	T <u>5N</u> R <u>16E</u>	<u>E-1</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Michael J. Rossow, in a field survey on April 15, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 1 CORNER, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A POST WAS SET AS CORNER (1817) WITH 2 BEARING TREE WITNESSES; A 14" SUGAR TREE N.65°E. 28 LINKS, AND A 13" BIRCH TREE N.48°W. 25 LINKS AND RECORDED THE OFFSET TO THE S.W. CORNER OF SEC. 33, T.6N., R.16E. AS 2.50 CHAINS. OLD ST. CLAIR COUNTY SURVEYOR'S RECORD SHOWS NO RECORD OF CORNER. NO ACT 74 CERTIFICATES REFERENCE THIS CORNER. NO ACT 132 CERTIFICATES REFERENCE THIS CORNER.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" REROD; 12" DEEP BETWEEN (33' EACH WAY) FENCES RUNNING EAST & WEST 66'± APART. OLD FENCE RUNS SOUTH ALONG EAST SIDE OF SECTION 5.

PA 345-1990
PEER COMMITTEE
APPROVED 7-11-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: *DEF.*

SET A 2" DIA. ALUMINUM CAP WITH MAGNET ATTACHED & INSCRIBED "ST. CLAIR COUNTY OFFICIAL CORNER" ON THE EXISTING 1/2" REROD AT THE CLOSING CORNER WHICH LIES 0.90' NORTH OF AND NORMAL TO A LINE BETWEEN THE SOUTHWEST CORNER OF SEC. 33 & THE S.W. CORNER OF SEC. 33, T.6N., R.16E.
12.15' NNE TO PK IN CO. TAG IN 6" ELM
23.39' WSW TO PK IN CO. TAG IN 12" ELM
20.21' SE TO PK IN CO. TAG IN 6" THORN APPLE
32.43' NNW TO PK IN CO. TAG IN 10" HICKORY

Signed by *[Signature]* Michael J. Rossow
Surveyor's Michigan License No. 24615

