



ST. CLAIR COUNTY, MICHIGAN
OFFICIAL GOVERNMENT CORNER

SURVEY &
REMONUMENTATION

MAR 15 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

CLERK REGISTER
ST. CLAIR COUNTY
RECEIVED FOR RECORD

DEC 22 1999

LIBER PAGE TIME 8:00 AM
Marilyn Quinn
MARILYN QUINN

Register of Deeds Stamp & File Number

Located In: ST. CLAIR TOWNSHIP Corner Code # F-13

1. Public Land Survey T 5N R 16E

2. Property Controlling in Section S T R

3. Miscellaneous Property in Sec. S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, MICHAEL J. ROSSOW, in a field survey on AUGUST 24, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 1 CORNER, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- F-13 ST. CLAIR TOWNSHIP, 1817, W. PRESTON OF GLO (MADE CORNER ON A 7" BLACKASH TREE)
 - (A) 1973, J. LANSKY LCRC L.1, P.596 (FINDS A CONCRETE MONUMENT & WITNESSES)
 - (B) 1972, R. SIDES SURVEY L.1, P.839 (IDENTIFIES CORNER AS "CONCRETE MONUMENT" WITH WITNESSES)
 - (C) 1997, M. ROSSOW SURVEY L.16, P.365 (REFERS TO LCRC L.1, P.596)
 - (D) 1984, ST. CLAIR COUNTY ROAD COMMISSION PLANS & WITNESSES
 - (E) 1942, OLD ST. CLAIR COUNTY SURVEYORS RECORD (SHOWS NOTHING FOR THIS CORNER (F-13))
- *SEE BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A 4" ROUND CONCRETE MONUMENT WITH WITNESSES FROM "A" ABOVE:
 NORTH 52.85' TO CENTERLINE OF CONCRETE PAVEMENT (A)(H)
 NORTH WEST 103.60' TO TAG IN DETROIT EDISON POLE (A)(D)(B)(E)(F)(H)
 SOUTH WEST 129.90' TO TAG IN DETROIT EDISON POLE (A)(B)(E)(F)(J)(H)
 CENTERLINE OF FRED W. MOORE HIGHWAY NORTH 52.85' (E)

THIS CORNER IS COMMON TO F-1 CHINA TOWNSHIP, T.4N, R.16E.

PA 345-1990
PEER COMMITTEE
APPROVED 12-15-99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET A 2" DIAMETER ALUMINUM CAP WITH MAGNET ATTACHED & INSCRIBED "ST. CLAIR COUNTY OFFICIAL CORNER" ON THE CONCRETE MONUMENT, WITH THE FOLLOWING WITNESSES:
 NORTH NORTH WEST 104.02' TO COUNTY TAG IN POWER POLE
 EAST NORTH EAST 291.56' TO COUNTY TAG IN POWER POLE
 EAST SOUTH EAST 284.33' TO COUNTY TAG IN POWER POLE
 SOUTH WEST 130.25' TO COUNTY TAG IN POWER POLE
 NORTH 40.76' TO SOUTH EDGE OF CONCRETE ON FRED W. MOORE HIGHWAY

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.



Signed by [Signature]
Surveyor's Michigan License No. 24615

Date 12-17-99



ST. CLAIR COUNTY, MICHIGAN
OFFICIAL GOVERNMENT CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
REMONUMENTATION

MAR 15 2000

SECTION

	Located In:	Corner Code #
	ST. CLAIR TOWNSHIP	
1. Public Land Survey	T <u>5N</u> R <u>16E</u>	<u>F-13</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- F-1 CHINA TOWNSHIP, 1817, W. PRESTON OF GLO (MADE CORNER ON A 7" BLACK ASH TREE)
- (F) 1972, R. SIDES LCRC L.1, P.550 (FINDS & WITNESSES A CONCRETE MONUMENT)(SAME AS LCRC AS L.1, P.596)
- (G) 1973, J. LANSKY LCRC L.1, P.596 (FINDS & WITNESSES A CONCRETE MONUMENT)
- (H) 1972, OLD ST. CLAIR COUNTY SURVEYORS RECORD (SHOWS NOTHING FOR THIS CORNER)(F-13)
- (I) 1973, J. LANSKY SURVEY L.5, P.136 (REFERS TO CERTIFICATE IN L.1, P.596)
- (J) 1972, R. SIDES SURVEY IN L.1, P.762 (FINDS CONCRETE MONUMENT & WITNESSES)
- (K) 1973, J. LANSKY SURVEY L.2, P.59 (REFERS TO A POINT 52.8' SOUTH OF CENTERLINE)
- (L) COUNTY ROAD COMMISSION (KREGER) 1960 WITNESSES

