

# ST. CLAIR COUNTY, MICHIGAN OFFICIAL GOVERNMENT CORNER



## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

	Located In:	Corner Code #	
1. Public Land Survey	T <u>6N</u> R <u>14E</u>	<u>K-1</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	<u>Seg. # 2</u>	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

REGISTER OF DEEDS  
ST. CLAIR COUNTY  
MICHIGAN

PA 345-1990-4  
M 10-23

REGISTER OF DEEDS STAMP & FILE NUMBER

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**Daniel E. Johnson**  
I, \_\_\_\_\_, in a field survey on May 23, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 1 corner, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
  
**LIBER 007 PAGE 281**

**STATE PLAIN COORDINATES**

N. \_\_\_\_\_  
E. \_\_\_\_\_

**ELEVATION** \_\_\_\_\_

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
  
**LIBER 007 PAGE 281**



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Removed boat spike. Set 1/2"x18" Rebar with 2" Dia. Aluminum Cap inscribed "St Clair County Official Corner" with magnet in monument box (2.14' South to line between section corners S $\frac{1}{4}$  36, SW 36, T.7N., R.14E.)  
149.24' ENE to set P.K. and County Tag in Tele Pole.  
190.37' SE to set P.K. and County Tag in Tele Pole.  
32.06' NE to set P.K. and County Tag in Tele and Light Pole.  
118.67' WNW to set P.K. and County Tag in Det. Ed. Pole.  
1.2' North to center of Asphalt Road

Signed by Daniel E. Johnson Date May 23, 1995  
Surveyor's Michigan License No. 13754

**PA 345-1990  
PEER COMMITTEE  
APPROVED 6-11-94**

APPROVED AS AN OFFICIAL GOVERNMENT CORNER BY ST. CLAIR COUNTY:  
Signed By: Daniel E. Johnson Date 7-25-95  
St. Clair County Land Surveyor Daniel E. Johnson  
13754