

**ST. CLAIR COUNTY, MICHIGAN
OFFICIAL GOVERNMENT CORNER**



**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Located In: _____ Corner Code # _____

- | | | |
|------------------------------------|--------------------------|---------------|
| 1. Public Land Survey | T <u>6N</u> R <u>15E</u> | <u>C-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | <u>Sec. 1</u> |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property In Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECEIVED
REGISTER OF DEEDS
ST. CLAIR COUNTY, MICHIGAN
1993 DEC 29 AM 9:08
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

David J. Little, in a field survey on Sept. 27-30, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 1 corner, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
Post-(Government Surveys)

Nothing listed on Old Surveyor's Record.
St. Clair County.

Nothing recorded for this corner.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Set "T" Iron Stamped LLS 31596.

Set "T" Iron on line with the S $\frac{1}{2}$ Corner Section 32, T7N, R15E and the N $\frac{1}{2}$ Corner Section 6, T6N, R15E and used Surveys by RLS 14760 and LLS 23510 to hold the West line Section 5, T6N, R15E and extended West line Section 5 North to intersect Township line.

2159A000 12/29/93 3508
0001

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

"T" Iron Stamped 31596

NE 126.10' to set P.K. and County Tag in W face of 60" Maple.
S. 52.48' to set P.K. and County Tag in E face of 18" Maple.
WSW 33.10' to set P.K. and County Tag in N face of 10" Poplar.
ESE 47.30' to set P.K. and County Tag in N face of 18" twin Maple.

See attached sketch for additional information.

2159A000 12/29/93 3508
0001

Signed by _____ Date December 10, 1993

David J. Little

Surveyor's Michigan License No. 31596

PA 345-1990

PEER COMMITTEE

APPROVED 12-14-93

APPROVED AS AN OFFICIAL GOVERNMENT CORNER BY ST. CLAIR COUNTY:

Signed By: _____ Date _____

St. Clair County Land Surveyor

Date

Surveyor's Michigan License No. _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

STATE PLAIN COORDINATES

N. _____

E. _____

ELEVATION _____

