

# ST. CLAIR COUNTY, MICHIGAN OFFICIAL GOVERNMENT CORNER



LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

	Located In:	Corner Code #	
1. Public Land Survey	T <u>6N</u> R <u>15E</u>	<u>D-1</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	<u>Seg. 1</u>	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

REGISTERED  
ST. CLAIR COUNTY  
1993 DEC 29 AM 9:04  
RECEIVED  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, David J. Little, in a field survey on Sept. 27-30, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 1 corner, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
**This Corner not set on Government Surveys.**  
  
**Nothing listed on Old Surveyor's Record.**  
**St. Clair County.**  
  
**Nothing recorded for this corner.**

STATE PLAIN COORDINATES

N. \_\_\_\_\_

E. \_\_\_\_\_

ELEVATION \_\_\_\_\_

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
**Location of Corner fall in the center of 20' wide creek and could not be set.**  
**Reference point "A" is a "T" Iron Stamped LLS 31596 and is 15.00' East of Corner and on the North line Section 5, T6N, T15E.**  
**Reference point "B" is a "T" Iron Stamped LLS 31596 and is 54.35' East of Corner and on the North line Section 5, T6N, R15E.**  
**Corner was established on line with the S $\frac{1}{4}$  Corner Section 32, T7N, R15E and the SE Corner Section 32, T7N, R15E and at equal between the NW Corner Section 5, T6N, R15E and the NE Corner Section 5, T6N, R15E.**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
**Reference point "A" "T" Stamped LLS 31596**  
**N. 21.0' to set P.K. and County Tag in E face 12" Maple**  
**NE 108.0" to set P.K. and County Tag in SW face of 12" Pine.**  
**SE 77.40' to set P.K. and County Tag in W face of 12 Ash**  
**SSE 18.15' to set P.K. and County Tag in NE face of 12" Mulberry**  
  
**Reference point "B" "T" Stamped LLS 31596**  
**WNW 36.2' to set P.K. and County Tag in E face of 12" Maple.**  
**NE 74.65' to set P.K. and County Tag in SW face of 12 Pine.**  
**SE 51.50' to set P.K. and County Tag in W face of 12 Ash.**  
**SW 83.33' to set P.K. and County Tag in NE face of 12" mulberry.**  
**See attached sketch for additional information.**



Signed by David J. Little Date December 10, 1993

Surveyor's Michigan License No. 31596

PA 345-1990  
PEER COMMITTEE  
APPROVED 12-14-93

APPROVED AS AN OFFICIAL GOVERNMENT CORNER BY ST. CLAIR COUNTY:

Signed By: \_\_\_\_\_  
St. Clair County Land Surveyor

Date \_\_\_\_\_  
LIBER 007 PAGE 175

Surveyor's Michigan License No. \_\_\_\_\_