

**ST. CLAIR COUNTY, MICHIGAN
OFFICIAL GOVERNMENT CORNER**



**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>15E</u>	<u>E-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	<u>Seg. 1</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED
 REGISTER OF DEEDS
 ST. CLAIR COUNTY, MICHIGAN
 1993 DEC 29 AM 9:04
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, David J. Little, in a field survey on October 6, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 1 corner, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
6" Beech (Government Surveys)
"T" Iron listed on Old Surveyor's Record St. Clair County.
"T" Iron is recorded in L.1 P.443-444(RLS 13042)

STATE PLAIN COORDINATES

N. _____
 E. _____
 ELEVATION _____

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found "T" Iron Bent-Re-set "T" Iron stamped LLS 315960001****

2159A000 12/29/93KSSU* 9.00

"T" Iron is on line between Southwest Corner Section 33, T7N, R15E and the Southeast Corner Section 33, T7N, R15E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set "T" Iron Stamped LLS 31596

SE 96.28' to set P.K. and County Tag in N. face of 15" Maple.
NE 143.0' to set P.K. and County Tag in S. face of 24" Maple.
NNW 231.70' to base of D.E. High Tension Power Line Tower leg set in conc.

2159A000 12/29/93SSRE* 2.00
 0001

See attached sketch for additional information.



Signed by David J. Little
 Surveyor's Michigan License No. 31596

Date December 1, 1993

PA 345-1990
 PEER COMMITTEE
 APPROVED 12-14-93

APPROVED AS AN OFFICIAL GOVERNMENT CORNER BY ST. CLAIR COUNTY:

Signed By: _____
 St. Clair County Land Surveyor

Date

Surveyor's Michigan License No. _____