

**ST. CLAIR COUNTY, MICHIGAN
OFFICIAL GOVERNMENT CORNER**



**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Located In: _____ Corner Code # _____

- | | | |
|------------------------------------|--------------------------|---------------|
| 1. Public Land Survey | T <u>6N</u> R <u>15E</u> | <u>G-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | <u>Seg. 1</u> |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous | S _____ T _____ R _____ | _____ |
| Property in Sec. | S _____ T _____ R _____ | _____ |

RECEIVED
 1993 DEC 29 AM 9:04
 REGISTER OF DEEDS
 ST. CLAIR COUNTY

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, David J. Little in a field survey on October 4, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 1 corner, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

8" B. Ash (Government Surveys)

Nothing listed on Old Surveyor's Record St. Clair County for this corner.

No Certificates filed on this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Set P.K. and Cap.

P.K. and Cap was set on line with the S. $\frac{1}{4}$ Corner Section 34, T7N, R15E and the SW Corner Section 34, T7N, R15E. Found P.K. 0.65' North in centerline of "Old M-21" and used P.K. for the West line Section 3 T6N, R15E extended.

2159A000 12/29/93KSSU4 9.00
~~2159A000~~ 12/29/93SSRE4 2.00
 0001

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
P.K. and Cap.

S. 67.30' to set P.K. and County Tag in the NE face of 12" Maple
 SW 59.0' to set P.K. and County Tag in NE face of 8" Maple.
 SE 72.35' to set P.K. and County tag in SW face of 12" Popular.

See attached sheet for additional information.



Signed by David J. Little
 David J. Little
 Surveyor's Michigan License No. 31596

Date November 20, 1993

PA 345-1990
 PEER COMMITTEE
 APPROVED 12-14-93

APPROVED AS AN OFFICIAL GOVERNMENT CORNER BY ST. CLAIR COUNTY:

Signed By: _____
 St. Clair County Land Surveyor

Date _____
 LIBER 007 PAGE 163

Surveyor's Michigan License No. _____