

ST. CLAIR COUNTY, MICHIGAN OFFICIAL GOVERNMENT CORNER



LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
REGISTERED DEEDS
ST. CLAIR COUNTY
93 DEC 29 AM 9:03

	Located In:	Corner Code #:	
1. Public Land Survey	T <u>6N</u> R <u>15E</u>	<u>K-1</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	<u>Seg-1</u>	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

David J. Little, in a field survey on October 6, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 1 corner, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

STATE PLAIN COORDINATES

Post-(Government Surveys)

N. _____

1" Iron in Monument Box listed on Old Surveyor's Record St. Clair County.

E. _____

1" Iron in Monument Box is recorded in L.2 P.184 and in L.2 P.402.

ELEVATION 59A000 12/29/93MSU04 11.00

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner 59A000 12/29/93SSU04 11.00

0003

Found 1" Iron in Monument Box appears to be 0.13 North of Corner.

59A000 12/29/93SSRE4 2.00

0003

Corner on Line with the SE corner Section 36 T7N, R15E and the SW corner Section 36 T7N, R15E.

Corner verified by 1930 Michigan State Highway Department plans.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Witnesses are to Corner which is 0.13 South of 1" Iron in Monument Box.

**SW 116.07' to set P.K. and County Tag in E. face of 12" Ash.
SSE 126.73' to set P.K. and County tag in W. face of D.E.P.
SE 58.48' to set P.K. and County Tag in W. face of D.E.P.
NE 71.40' to set P.K. and County Tag in SE face of tele.pole
(Corner is on the centerline of existing Lapeer Road pavement)**



See attached sketch for additional information.

Signed by David J. Little
David J. Little

Date November 20, 1993

Surveyor's Michigan License No. 31596

PA 345-1990

PEER COMMITTEE

APPROVED AS AN OFFICIAL GOVERNMENT CORNER BY ST. CLAIR COUNTY:

APPROVED 12-7-93

Signed By: _____
St. Clair County Land Surveyor

Date

Surveyor's Michigan License No. _____