

**ST. CLAIR COUNTY, MICHIGAN
OFFICIAL GOVERNMENT CORNER**



**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

	Located In:	Corner Code #
	Wales Twp.	
1. Public Land Survey	T <u>6N</u> R <u>15E.</u>	<u>M-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	<u>Seg. 1</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED
 1993 DEC 29 AM 03
 REGISTER OF DEEDS
 ST. CLAIR COUNTY, MICHIGAN
 Register of Deeds, Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John R. Lansky in a field survey on Sept. 20-24, 1993 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 1 corner, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1. Post-- Original Gov't Survey
 2. Nothing Listed on Old Surveyor's Record
St. Clair County for this corner.
 3. Iron Rod Per Certificate L. 6 P.66

STATE PLAIN COORDINATES
 N. _____
 E. _____
 ELEVATION _____

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found Iron Rod w/Cap RLS 19835 (Damaged Cap)

2159A000 12/29/93HSSU# 9.00
 0001
 2159A000 12/29/93SSRE# 2.00
 0001

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Iron Rod with Cap RLS 19835
 N.E. 42.53 ft. Set PK nail & tag in 8" Elm
 S.E. 57.15 ft. " " " in 12" Elm
 S.W. 137.05 ft. found spike/Cap RLS 18659 in D.E. Pole
 S.'ly 57.94 ft. to S.W. Cor. Sec. 7, T.6N., R.16E.



See attached sketch for additional information.

Signed by John R. Lansky Date Sept. 29, 1993
 Surveyor's Michigan License No. 18659

PA 345-1990
 PEER COMMITTEE
 APPROVED 11-23-93

APPROVED AS AN OFFICIAL GOVERNMENT CORNER BY ST. CLAIR COUNTY:

Signed By: _____ Date _____
 St. Clair County Land Surveyor
 Surveyor's Michigan License No. _____