

**ST. CLAIR COUNTY, MICHIGAN
OFFICIAL GOVERNMENT CORNER**



**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

	Located In:	Corner Code #
	Wales Twp.	
1. Public Land Survey	T <u>6N</u> R <u>15E</u>	<u>M-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	<u>Sec. 1</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED
REGISTERED DEEDS
ST. CLAIR COUNTY
1993 DEC 29 AM 9:00
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	15	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John R. Lansky, in a field survey on Sept. 14-18, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 1 corner, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1.13" White Ash-- Per Original Gov't Survey
- Concrete Mon. Per Old Surveyor's Rec. St. Clair Co.
- Conc. Mon. Per Certificate Rec. L.7 P.63

STATE PLAIN COORDINATES

N. _____
E. _____
ELEVATION _____

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found Concrete Monument.

2159A000 12/29/93KSSU# 9.00
000J
2159A000 12/29/93SSRE# 2.00
000J

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Concrete Monument (In Monument Box)

- S.E. 80.05 Set PK nail & County Tag in D.E. Pole
- S.W. 50.6 ft. " " " " "
- South 11.7 ft. to centerline of Exist. Asph. Pav't.
- S.W. 55.1 ft. to Found Red Top Mon (damaged) (1936 Witness)
- S.E. 45.5 ft. to center of S.E. Mich. Gas Pipeline marker.
- See Attached sketch for additional information.



Signed by John R. Lansky Date Sept. 20, 1993

Surveyor's Michigan License No. 18659

PA 345-1990
PEER COMMITTEE

APPROVED 11-16-93

APPROVED AS AN OFFICIAL GOVERNMENT CORNER BY ST. CLAIR COUNTY:

Signed By: _____ Date _____
St. Clair County Land Surveyor

Surveyor's Michigan License No. _____