

ST. CLAIR COUNTY, MICHIGAN OFFICIAL GOVERNMENT CORNER



LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

	Located In: Kimball Twp.	Corner Code # A-5
1. Public Land Survey	T <u>6N</u> R <u>16E</u> .	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

RECEIVED
 1993 DEC 29 AM 9:03
 REGISTER OF DEEDS
 ST. CLAIR COUNTY
 Register of Deeds, Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, John R. Lansky, in a field survey on Sept. 20-24, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 1 corner, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1. Post-- Original Gov't Survey
 2. Stone-- Per Old Surveyor's Rec. St. Clair Co.
 3. "T" Iron Per Certificate L.2 P.239

STATE PLAIN COORDINATES

N. _____

E. _____

ELEVATION _____

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found "T" Iron (Cap Missing) Per Certificate

2159A000 12/29/93MSSU# 9.00
 0001

2159A000 12/29/93SSRE# 2.00
 0001

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:



"T" Iron
 E.N.E. 38.53 ft. Set PK Nail & Tag in 12" Elm
 N.E. 90.52 ft. " " " in 8" Elm
 S.W. 81.7 ft. Found Spike & Cap (RLS 18659) in D.E. Pole
 Northerly 57.94 ft. to N.E. Cor. Sec. 13, T.6N., R.15E.

See attached sketch for additional information.

Signed by John R. Lansky
 John R. Lansky
 Surveyor's Michigan License No. 18659

Date Sept. 29, 1993

PA 345-1990
 PEER COMMITTEE

APPROVED 11-23-93

APPROVED AS AN OFFICIAL GOVERNMENT CORNER BY ST. CLAIR COUNTY:

Signed By: _____ : _____
 St. Clair County Land Surveyor Date

Surveyor's Michigan License No. _____