

**ST. CLAIR COUNTY, MICHIGAN
OFFICIAL GOVERNMENT CORNER**



**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED
REGISTER OF DEEDS
ST. CLAIR COUNTY
1993 DEC 29 AM 9:00

Register of Deeds Stamp & File Number

	Located In:	Corner Code #
	Kimball Twp.	
1. Public Land Survey	T <u>6N</u> R <u>16E.</u>	<u>A-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	<u>Seg-1</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	25	25						
11												
12	31	32	33	34	35	36						
13												

I, John R. Lansky in a field survey on Sept. 14, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 1 corner, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 3" Ironwood. Per Original Gov't Survey.
- Concrete Monument (Per County Rec. 1936)

Note: Corner is common to four townships.

STATE PLAIN COORDINATES

N. _____

E. _____

ELEVATION _____

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Concrete Monument with iron rod inserted to raise to surface grade.

Note: This monument agrees with location on certificate filed by RLS 24608 (L.6 P.67) but does not agree with location on certificate filed by RLS 24601 (L.6 P.134), that point lies S.E.'ly 4.27 ft. from conc. monument and was set for a P.I. on road construction. (Ref A.D. Plans Rds 53 and 106)


2159A000 12/29/93HSSU# 9.00
000J

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Concrete Monument with Iron rod inserted

2159A000 12/29/93HSSU# 2.00
000J

- N.W. 43.57 Set PK Nail with County Tag in D.E. Pole
 - N.E. 67.8 ft. to center of Sun Pipe line marker.
 - S.E. 77.4 ft. to N.W. Corner of N/S Conc. Headwall
 - S.W. 77.7 ft. to the N.E. Corner of N/S. Conc. Headwall.
- (See attached sketch for additional information).



Signed by John R. Lansky
Surveyor's Michigan License No. 18659

Date Sept. 20, 1993

PA 345-1990
PEER COMMITTEE

APPROVED AS AN OFFICIAL GOVERNMENT CORNER BY ST. CLAIR COUNTY:

APPROVED 11-30-93

Signed By: _____
St. Clair County Land Surveyor

Date _____

Surveyor's Michigan License No. _____