

**ST. CLAIR COUNTY, MICHIGAN
OFFICIAL GOVERNMENT CORNER**



**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SURVEY &
REMONUMENTATION

DEC 02 1997

COMMISSION

	Located In:	Corner Code #
	KIMBALL TWP.	
1. Public Land Survey	T <u>6N</u> R <u>16E</u>	<u>D-13</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED
ST. CLAIR COUNTY
REGISTER OF DEEDS
97 AUG 21 AM 7:25

Register of Deeds Stamp & File Number

I, Michael J. Rossow, in a field survey on April 08, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 1 CORNER, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
A POST WAS SET FOR THIS CORNER IN ORIGINAL GOVERNMENT SURVEY (1817) WITH THE FOLLOWING BEARING TREES: 18" WHITE OAK S.11°E. 27 LINKS AND A 30" WHITE OAK N.85°E. 20 LINKS BOTH OF WHICH ARE GONE. THE OLD ST. CLAIR COUNTY SURVEYOR'S RECORD SHOWS NO WITNESSES NOR CORNER (1942). AN ACT 74 CERTIFICATE WAS FILED IN L.2,P.367 (1974) AND IDENTIFIES A CONCRETE MONUMENT AS THE CORNER. CORNER WAS WITNESSED BY ST. CLAIR COUNTY ROAD COMMISSION IN THEIR CORNER BOOK PAGE 120.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND A CONCRETE MONUMENT PER ACT 74 CERTIFICATE FILED IN L.2,P.367

- 28.66' N.E. TO CONCRETE MON. FOUND AND VERIFIED.
- 25.77' N.W. TO CONCRETE MON. FOUND AND VERIFIED.
- 15.90' S.E. TO CONCRETE MON. FOUND AND VERIFIED, 16.0' MEASURED
- 23.70' S.W. TO CONCRETE MON. FOUND AND VERIFIED, 23.65' MEASURED

PA 345-1990
PEER COMMITTEE
APPROVED 7-11-97
DSEY.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET A 2" DIA. ALUMINUM CAP WITH MAGNET ATTACHED & INSCRIBED "ST. CLAIR COUNTY OFFICIAL CORNER" ON THE EXISTING 3/4" PIPE WHICH IS ENCASED AS A CONCRETE MONUMENT. THIS CORNER IS 124.08' WEST OF THE N. ¼ CORNER OF SEC. 5, T.5N., R.16E. S.87°25'10"W. 2657.90' TO THE S.W. COR. SEC. 32, STATE PLANE COORDINATES N.86°38'37"E. 2718.56' TO THE S.E. COR. SEC. 32, STATE PLANE COORDINATES N. 27.75' PK AND COUNTY TAG IN 12" ASH S. 42.90' PK AND COUNTY TAG IN 10" ELM W.N.W. 67.94' PK AND COUNTY TAG IN 18" TRIPLE ASH N.E. 35.83' PK AND COUNTY TAG IN MULTI MAPLE

Signed by *[Signature]* Michael J. Rossow Date _____
Surveyor's Michigan License No. 24615

