

SURVEY &  
REMONUMENTATION

# ST. CLAIR COUNTY, MICHIGAN OFFICIAL GOVERNMENT CORNER



DEC 02 1997

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

REGISTERED  
ST. CLAIR COUNTY  
MAY 21 AM 7:25

	Located In:	Corner Code #
	KIMBALL TWP.	
1. Public Land Survey	T <u>6N</u> R <u>16E</u>	<u>G-13</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Michael J. Rossow, in a field survey on April 29,  
1997, do hereby certify that under requirements of P.A. 74, Michigan P.A.  
of 1970, the corner points mentioned in lines 1 and 2 above were in  
conformance with regulations and rules therefore as required in the current  
manual of survey instructions of the United States Department of the Interior,  
Bureau of Land Management or by a decree of a Court of Law and/or that the  
corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of  
Law; established, re-established, monumented, re-monumented, recovered,  
found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 1 CORNER, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

A 4" IRONWOOD TREE WAS MARKED AS CORNER IN ORIGINAL GOVERNMENT SURVEY WITH NO BEARING  
TREES RECITED (1817). OLD ST. CLAIR COUNTY SURVEYOR'S SHOW NOTHING FOR THIS CORNER  
NOR WITNESSES NOTHING. ACT 74 CERTIFICATES FILED IN L.4,P.65 & L.8,P.254 (1996)  
L.4,P.65 IDENTIFIES A "WOOD POST" AS CORNER WITH ONE REMAINING WITNESSES: L.8,P.254  
IDENTIFIES AN IRON ROD WITH #19835 IDENTIFIER WITH WITNESSES THAT AGREE WITH  
L.4,P.65.

PA 345-1990  
PEER COMMITTEE  
APPROVED 7-11-97  
DESJ.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND IRON 1/2" REBAR PER ACT 74 CERTIFICATES: L.4,P.65 RECORDED WITNESSES: 1348.1'  
WEST OF CENTER SCOTT RD.; VERIFIED 1350.6' MEASURED  
147.8' WEST OF G-1 OF ST. CLAIR TWP.; VERIFIED, 147.43' MEASURED  
L.8,P.254 RECORDED WITNESSES:  
NORTH 19.90' TO SPIKE AND CAP IN 12" RED OAK FOUND & VERIFIED, 19.73' MEASURED  
NORTHEAST 18.50' TO SPIKE AND CAP IN 12" RED OAK FOUND & VERIFIED, 18.21' MEASURED  
EAST 147.43' TO NORTHWEST CORNER SEC. 3, T.5N.,R.16E., VERIFIED, 147.11' MEASURED

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

SET A 2" DIA. ALUMINUM CAP WITH MAGNET ATTACHED & INSCRIBED "ST. CLAIR COUNTY  
OFFICIAL CORNER" ON THE EXISTING 1/2" REBAR.  
S.86°42'36"W. 2700.30' TO THE S. 1/4 COR. SEC. 33, STATE PLANE COORDINATES  
N.86°20'46"E. 2682.46' TO THE S. 1/4 COR. SEC. 34, STATE PLANE COORDINATES  
147.11 W. OF THE NORTHEAST CORNER OF SEC. 4, T.5N.,R.16E.  
SOUTH 21.80' PK AND COUNTY TAG IN 15" ASH  
S.W. 19.15' PK AND COUNTY TAG IN 10" ELM  
N.W. 38.30' PK AND COUNTY TAG IN 6" RED OAK  
NORTH 19.77 PK AND COUNTY TAG IN 15" RED OAK

Signed by \_\_\_\_\_ Michael J. Rossow Date August 1997  
Surveyor's Michigan License No. 24615

