

ST. CLAIR COUNTY, MICHIGAN OFFICIAL GOVERNMENT CORNER



LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

| | | | |
|---------------------------------------|-----------------------------|---------------|--|
| | Located in: Kimball Twp. | Corner Code # | |
| 1. Public Land Survey | T <u>6N</u> R <u>16E</u> | A-11 | |
| | T _____ R _____ | | |
| | T _____ R _____ | | |
| | T _____ R _____ | | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | <i>Seg 2</i> | |
| | S _____ T _____ R _____ | | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | | |
| | S _____ T _____ R _____ | | |
| 4. Lot No. _____, Recorded Plat _____ | | | |
| 5. Private Claims _____ | | | |

RECEIVED
 REGISTER OF DEEDS
 ST. CLAIR COUNTY
 1995 AUG -4 AM 10:18

Register of Deeds Stamp & File Number

I, Daniel E. Johnson in a field survey on May 11, 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | ● | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 1 corner, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 SEE LIBER 007 PAGE 389
 Corner marked on a 6" hornbeam tree by William Preston, 1817. Large stone with crockery around found by M.O. Peck in 1936 and replaced with concrete monument. Concrete monument recovered and witnessed by Mark Witalec in 1983 Sr. Clair County Road Comm. Corner Book. Concrete monument in monument box recovered and recorded by C. McDaniel, Liber 6, Page 282 in 1990.

STATE PLAIN COORDINATES
 N. _____
 E. _____
 ELEVATION _____

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 SEE LIBER 007...PAGE 389
 Found concrete monument in monument box. Verified corner from previously set witnesses. Also referenced St. Clair County Road Comm. corner records, recorded surveys by R. Kreger, Liber 8, page 230 and G. James Liber 6, page 125. D. Little set a "T" iron 4.65 feet east of the recorded concrete monument, Liber 7, page 65 in 1993. This point marks the intersection of the true range line and section line to the east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set 2" dia aluminum cap inscribed "St. Clair County Official Corner" with magnet on a concrete monument in monument box on centerline of Mayer Road located 4.65 feet west of true range line. S.E. 47.10' to set P.K. Nail with county remon tag in W. side of power pole. W.N.W. 34.96' to set P.K. Nail with county remon tag in S. side of power pole. N. 30.0' to centerline of Smith Creel Road pavement. E. 49.93' to center of U.S.G.S. concrete monument with brass disc. S. 2680.20' to the W 1/4 corner of Section 31, T6N-R16E. N. 2709.51' to the W 1/4 corner of Section 30, T6N-R16E



Signed by Daniel E. Johnson Date May 11, 1995

Surveyor's Michigan License No. 13754

PA 345-1990
PEER COMMITTEE

APPROVED AS AN OFFICIAL GOVERNMENT CORNER BY ST. CLAIR COUNTY:

Signed By: Daniel E. Johnson : 7-31-95
 St. Clair County Land Surveyor

APPROVED 6-24-94
Dan J
 Date 7-31-95
 LIBER 008 PAGE 135

Surveyor's Michigan License No. _____