

# ST. CLAIR COUNTY, MICHIGAN OFFICIAL GOVERNMENT CORNER



## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Located In: Kimball Twp. Corner Code # L-1

- |                                    |                            |               |
|------------------------------------|----------------------------|---------------|
| 1. Public Land Survey              | T <u>6N.</u> R <u>16E.</u> | <u>L-1</u>    |
|                                    | T _____ R _____            | _____         |
|                                    | T _____ R _____            | _____         |
|                                    | T _____ R _____            | _____         |
| 2. Property Controlling in Section | S _____ T _____ R _____    | <u>Sec. 2</u> |
|                                    | S _____ T _____ R _____    | _____         |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____    | _____         |
|                                    | S _____ T _____ R _____    | _____         |

RECEIVED  
1995 AUG -4 AM 10:11  
REGISTER OF DEEDS  
ST. CLAIR COUNTY  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Daniel E. Johnson in a field survey on May 25, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 1 corner, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

**LIBER 007 PAGE 352**

STATE PLAIN COORDINATES

N. \_\_\_\_\_

E. \_\_\_\_\_

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**LIBER 007 PAGE 352**

ELEVATION \_\_\_\_\_



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1/2"x18" Rod with 2" dia. aluminum cap inscribed "St. Clair County Official Corner" with magnet (in monument box)  
1.2' south of exist. centerline of W Water St. Pvmt. Located 1.74 feet south of the true Township line.  
N 55°E 63.34' to set PK nail w/county remon tag in NW side power pole  
N 21°W 61.93' to set PK nail w/county remon tag in W side 24" Ash Tree  
S 29°W 56.65' to set PK nail w/county remon tag in NW side 24" Oak Tree  
S 15°E 52.35' to set PK nail w/county remon tag in W side 24" Oak Tree  
WEST 2771.70' to NW corner Section 1, T6N-R16E  
EAST 2768.57' to NE corner Section 1, T6N-R16E

Signed by Daniel E. Johnson Date May 25, 1995

Surveyor's Michigan License No. 13754

PA 345-1990  
PEER COMMITTEE

APPROVED AS AN OFFICIAL GOVERNMENT CORNER BY ST. CLAIR COUNTY:

Signed By: Daniel E. Johnson Date 7/31/95

St. Clair County Land Surveyor Daniel E. Johnson

Surveyor's Michigan License No. 13754

LIBER 008 PAGE 131