

ST. CLAIR COUNTY, MICHIGAN OFFICIAL GOVERNMENT CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970



RECEIVED
 MARY V. DUNN
 REGISTER OF DEEDS
 ST. CLAIR COUNTY
 1996 JUL 31 AM 8:01

Register of Deeds Stamp & File Number

	Located In:	Corner Code #	
	Brockway Township		
1. Public Land Survey	T <u>8N</u> R <u>14E</u>	<u>M-13</u>	
	T _____ R _____		
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, John C. Niederhauser, in a field survey on April 23, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 1 corner, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Joseph Wampler set a wood post in 1822 as the original government corner. It is a common corner to four (4) townships per the original field notes. Reference corners A-13 of T8N R15E, A-1 of T7N-R15E, and M-1 of T7N-R14E. C. Alloway recovered and recorded a P.K. nail, L.C.R.C. Liber 4, Page 176. C. McDaniel recovered a P.K. nail and set and recorded a R.R. spike, L.C.R.C. Liber 6, Page 335. J. Niederhauser found and recorded a railroad spike L.C.R.C. Liber 6, Page 391. Also referenced BMJ surveys dated 6-1-1989, 11-11-1991 and 8-5-1993; Collins surveys 11-23-1979 and 7-10-1974; Alloway surveys dated 9-14-1975 and 2-10-1976. 3/4" pipe listed on Old County Surveyor's Record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found railroad spike on centerline of Metcalf Road pavement east and west and Cork Road to south and old fence line to the north. Verified corner from found witnesses on recorded L.C.R.C. Liber 6, Page 391. Replaced railroad spike with a 1/2" iron rorod and 2" diameter aluminum cap inscribed "St. Clair County Official Corner" set in a new monument road box.

SURVEY &
REMONUMENTATION

JUL 14 1997

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a 2" diameter aluminum cap with a magnet attached and inscribed "St. Clair County Official Corner" on a 1/2" iron rorod in a new monument road box. This corner marks the intersection of four (4) townships. For additional information reference corners A-13 of T8N-R15E, A-1 of T7N-R15E and M-1 of T7N-R14E.

- N. 29.78' to set P.K. nail with county remon. tag in east side power pole.
- N.E. 99.81' to set P.K. nail with county remon. tag in south side 8" Boxelder tree.
- S.S.E. 101.94' to set P.K. nail with county remon. tag in west side 10" Ash tree.
- S.S.W. 93.49' to set P.K. nail with county remon. tag in the east side at the northeast corner of a wood barn.
- East 2542.62' to the north quarter corner of Section 6, T7N-R15E.
- South 2458.30' to the west quarter corner of Section 6, T7N-R15E.

PA 345-1990
PEER COMMITTEE

APPROVED 7-12-96

Signed by [Signature] Date 7-12-96

Surveyor's Michigan License No. 24608

