



ST. CLAIR COUNTY, MICHIGAN
OFFICIAL GOVERNMENT CORNER



LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

	Located In:	Corner Code #
	Greenwood Township	
1. Public Land Survey	T <u>8N</u> R <u>15E</u>	<u>M-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED
MARTIN GUNN
1996 JUL 31 AM 8:00
REGISTER OF DEEDS
ST. CLAIR COUNTY

Register of Deeds Stamp & File Number

I, John C. Niederhauser, in a field survey on April 1, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					

NOTE: Not more than 1 corner, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Joseph Wampler set a wood post in 1822 as the original government corner. It is a common corner to four (4) townships per the original field notes. Reference corners: A-13 of T9N-R16E, A-1 of T8N-R16E and M-13 of T9N-R15E. Nothing listed on Old County Surveyors Record. Buckley Collins P.S. recovered and recorded a steel rod on 8/27/1974, see survey Liber 3, Page 87 and LCRC Liber 4, Page 218. Robert Kreger P.S. recovered and recorded a 5/8" iron rered on 6/10/1980, see Liber 7, Page 370. John Milletics, P.S. recovered and recorded a 1/2" bar on 10/25/1993, see F-2050 at Lands and Graphics Department.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" iron rered on the center line of intersection of Fisher Road (gravel), east and west and Cribbins Road (gravel), north and south. Could not locate any previously recorded witnesses. Verified corner from distances listed on Milletics survey and Kreger survey.

SURVEY &
REMONUMENTATION

JUL 14 1997

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a 2" diameter aluminum cap with a magnet attached and inscribed "St. Clair County Official Corner" on the existing 5/8" iron rered. This corner marks the intersection of four (4) townships. For additional information reference corners: A-13 of T9N-R16E, A-1 of T8N-R16E and M-13 of T9N-R15E. South 33° E 87.71 feet to set P.K. nail with county remon tag in west side 12" Elm tree. South 84° W 140.68 feet to a chiseled "X" on the east end of the south headwall. North 38° E 60.82 feet to set P.K. nail with county remon tag in east side 4" Elm tree. North 34° W 61.90 feet to set P.K. nail with county remon tag in east side power pole. South 2568.51 feet to found 1/2" rered on center line Cribbins Road and tree line east. East 2552.31 feet to found 1/2" rered on center line Fisher Road and tree line south. West 2634.61 feet to found 1/2" rered on center line Fisher Road and tree line north.

PA 345-1990
PEER COMMITTEE

APPROVED 7-19-96
Daniel E. Johnson

Signed by _____ Date July 18, 1996

Surveyor's Michigan License No. 24608

LIBER 008 PAGE 274