

REMONUMENTATION

NOV 04 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 4 PAGE 338

For corners in

ST. JOSEPH	Located In:	Corner Code #
(County)		
LEONIDAS TWP.		
1. Public Land Survey	T 5S R 9W	A-2
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED

20 MAY 97 11:54 A.M.

CYNTHIA JARRATT
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, WAYNE A. MOSTROM, in a field survey on MAY 8, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
NO OLD RECORDS FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 3/4" X 22" PIPE OVER +D STONE 30" DEEP
APPROX. 3' WEST OF Q MCCLISH RD. & IN FENCE TO EAST.
MENDON CORNER (PIPE OVER STONE) IS 24.84' SOUTH

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON MAY 12, 1997
K. Buss CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET 5/8" X 18" BAR & STD. CAP OVER +D STONE IN MON. BOX
N & W IN NE SIDE 20" OAK = S45°E 41.44'
N & W IN N. SIDE P.P. = N85°E 46.47'
N & W IN SW SIDE P.P. = N59°W 37.53'
NE COR. RR RAIL POST = S89°W 25.53'



LIBER 4 PAGE 338

Signed by Wayne A. Mostrom
Surveyor's Michigan License No. 14100

Date 5/16/97

NOV 4 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN. 1983
REVISED OCT., 1985

REMONUMENTATION

1st Cor. in 1997 2nd Report