

NOV 04 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

COMMISSION

LIBER 4 PAGE 341

<u>ST. JOSEPH</u> (County)	Located In:	Corner Code #
LEONIDAS TWP.	T <u>5S</u> R <u>9W</u>	<u>C-2</u>
1. Public Land Survey	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED

20 MAY 97 11:56 A.M.

CYNTHIA JARRATT
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, WAYNE A. MOSTROM, in a field survey on MAY 8, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		⊙	5		4		3		2		1	
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

<u>GLO</u>	<u>1865 SURVEY IN A/117</u>
16" SUGAR = S22°E 0.09 CH.	STONE SET FROM OLD BEARINGS
5" BEECH = N60°W 0.11 CH.	9" ELM = N80°E 54 LKS.

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON MAY 12, 1997
Wayne CO. REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND STONE (KNOCKED OVER) AND SEVERAL PIECES OF BRICK
1' WEST OF \odot OF ASPHALT IN FENCE LINE TO WEST
DURING LARGE EXCAVATION WITH COUNTY BACKHOE
STONE PLACED IN UPRIGHT POSITION FALLS IN APPROXIMATE CENTER
OF BRICK PIECES FOUND. STONE UPRIGHTED IS 2654.4'± NORTH OF
STONE FOUND AT SE COR. OF SEC. (1865 SURVEY SHOWS 2652.21)
GRADE IS HILLY.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" X 24" BAR W/STD. CAP IN MON. BOX
(REMOVED STONE)
FACE OF RR RAIL POST = S89°E 32.93'
N & W IN S. SIDE 26" MAPLE = N82°E 35.29'
N & W IN SE SIDE 22" MAPLE = N58°E 40.92'
N & W IN NE SIDE 16" TRI-MAPLE = N23°W 82.16'
N & W IN SE SIDE WOOD A.P. = S88°W 30.09'

Signed by Wayne A. Mostrom
Surveyor's Michigan License No. 14100

Date 5.17.97

