

NOV 04 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION

LIBER 4 PAGE 342

<u>ST. JOSEPH</u> (County)	Located In:	Corner Code #
<u>LEONIDAS TWP.</u>		
1. Public Land Survey	T <u>5S</u> R <u>9W</u>	<u>C-3</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN
ST. JOSEPH COUNTY
FILED

20 MAY 97 11:56 A.M.

CYNTHIA JARRATT
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, WAYNE A. MOSTROM, in a field survey on MAY 8, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3			⊙										
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

<u>GLO</u>	<u>1865 SURVEY IN 1/116</u>	<u>1926 ROAD SURVEY BY MCCOY</u>
9" BEECH = N18°E 15 LKS.	STAKE SET FROM OLD BEARINGS	SHOWS STONE IN N-S CENTERLINE
9" BEECH = S83°W 27 LKS.		AND A SHORT DISTANCE NORTH OF
		E-W CENTERLINE OF ROADS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DUG WITH COUNTY ROAD COMMISSION BACKHOE.
FOUND LARGE STONE (KNOCKED OVER) 4' NORTH OF C
INTER. OF ROADS
SET STONE UPRIGHT

RATIFIED BY PEER GROUP
IN ACCORDANCE WITH P.A. 345
ON MAY 12, 19 97
Wayne CO. REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" X 12" BAR WITH STD. CAP OVER STONE IN MON. BOX
SW COR. RR RAIL POST = S43°E 51.58'
NW COR. RR RAIL POST = S40°W 48.63'
N & W IN SE SIDE P.P. = N49°E 49.12'
N & W IN SW SIDE 60" SYCAMORE = N14°E 129.48'



Signed by Wayne A. Mostrom
Surveyor's Michigan License No. 14100

Date 5/17/97

LIBER 4 PAGE 342