

**SURVEY & REMONUMENTATION**

NOV 30 1993

004 PG 006

FILED

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

JUL 27 1 03 PM '93

*Cynthia R. Janett*  
REGISTER OF DEEDS  
ST. JOSEPH CO MICH

corners in  
T. JOSEPH  
(County)  
EONIDAS TWP.  
Public Land Survey  
Property Controlling  
in Section  
Miscellaneous  
Property in Sec.

Located In: T 5S R 9W  
T R  
T R  
T R  
S T R  
S T R  
S T R  
S T R

Corner Code # C-11

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

WAYNE A. MOSTROM, in a field survey on MAY 10, MAY 13, 1993, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as pressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

OLD SURVEY - 1835 SAYERS - 1969 & L.C.R.C. - 3/002  
 " Y.O. = S15°E 33 LKS OLD COR. WAS DUG FOR - NOTHING FOUND. NO RECORDS IN OLD SURVEY BOOKS.  
 " W.Y. = N51½°W 56 LKS SET BY DOUBLING DIST. BWT. STONES FD. ¼ & ½ MI. TO SOUTH  
 SURVEYS IN OLD SE COR. BARN = NW 47.7'  
 COURTHOUSE BOOKS POST = SW 42'  
 30" MAPLE = SE 39.72'

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

IRON BAR CAPPED #7874 (SAYERS)  
 COR BARN = NW 47.70'  
 ST & MAPLE TREE WERE OUT.  
 ST. & LINE WAS CHECK FROM STONE ½ MI & ¼ MI SOUTH  
 R. IS O.K. ON DOUBLED DIST.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

COMMON TO SEC.'S 29, 30, 31, 32  
 5/8"X24" IRON BAR W/STD. COUNTY CAP  
 COR. BARN = N15°W 47.60'  
 IN SE SIDE BLK. LOCUST = N21°E 45.5'  
 RAIL POST = S57°E 55.45'  
 IN P.P. = S45°E 69.50'  
 IS 4' N & 4' E OF 2 GRAVEL ROADS & IN FENCE TO NORTH



APPROVED BY PEER GROUP AS ACCEPTED RE-ESTABLISHMENT OF ORIGINAL CORNER

Surveyed by *Wayne A. Mostrom*

Date JULY 19, 1993

Surveyor's Michigan License No. 14100