

SURVEY & REMONUMENTATION

NOV 30 1993

COMMISSION

004 PG 011

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

OCT 7 11 05 AM '93

Cynthia R. Isenett
REGISTER OF DEEDS
ST. JOSEPH CO MICH

or corners in

ST. JOSEPH
(County)

Located In:

Corner Code ~~##~~

LEONIDAS TWP.
Public Land Survey

T 5S R 9W C-12
T _____ R _____
T _____ R _____
T _____ R _____
T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____

Property Controlling
in Section
Miscellaneous
Property in Sec.

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

WAYNE A. MOSTROM, in a field survey on SEPT. 13, 1993,
hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

GLO NO ROAD COMM. RECORDS
16" W.O. = S51½°W 2.21' CH.
1886 SURVEY BY TODD - A/532
SHOWS CORNER TO BE USED
DOES NOT IDENTIFY IT
SAYERS 1979 SURVEY & L.C.R.C. - 3/002
FOUND STONE
18" HICK. = SE 65'
RR RAIL POST = EAST 25'
RR RAIL POST = WEST 17.2'

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND ROTTED REMAINS OF 18" HICK. SE 65'
R.R. RAIL POST = EAST 25'
R.R. RAIL POST = WEST 17.2'



Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REMOVED STONE & SET 5/8" X 24" BAR W/STD. CAP IN MON. BOX
FACE R.R. RAIL POST = EAST 25.86'
FACE R.R. RAIL POST = WEST 17.11'
N&W IN NE SIDE 24" W.O. = N70°W 42.78'
N&W IN S SIDE 24" HICK = N50°W 80.74'
N&W IN E SIDE DBL. 22" BLK. OAK = N40°W 53.68'

APPROVED BY PEER GROUP AS
ACCEPTED PERPETUATION OF
ORIGINAL CORNER

Signed by Wayne A. Mostrom
Surveyor's Michigan License No. 14100

Date Oct 1, 1993 MISC. 7.00
2558 000011 10-7-93